

PAVING SCHEDULE

STATION TO STATION	LENGTH	PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA SURFACE COURSE, MIX "C", N70	HMA SURFACE COURSE, MIX "D", N90	LEVELING BINDER (MACHINE METHOD), N70	LEVELING BINDER (MACHINE METHOD), N90	HMA SURFACE REMOVAL - BUTT JOINT	HMA SURFACE REMOVAL, 1/2	HMA SURFACE REMOVAL, 2 1/4	HMA SURFACE REMOVAL, VARIABLE DEPTH	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP (SPECIAL)	TEMPORARY RAMP
1015+10.00 TO 1020+45.00	535.0	27.0	1605.0	160.5	3.2	134.8	-	67.4	-	135.0	1605.0	-	-	36.1	-	37.5
1020+45.00 TO 1024+47.20	402.2	33.0	1474.7	147.5	2.9	123.9	-	61.9	-	-	1474.7	-	-	27.1	-	-
1025+05.30 TO 1031+20.00	614.7	39.0	2663.7	266.4	5.3	223.8	-	111.9	-	-	2663.7	-	-	41.5	-	-
1031+20.00 TO 1034+50.00	330.0	33.0	1210.0	121.0	2.4	101.6	-	50.8	-	-	1210.0	-	-	22.3	-	-
1034+50.00 TO 1218+55.00	18405.0	27.0	55215.0	5521.5	110.4	4638.1	-	2319.0	-	-	55215.0	-	-	1242.3	-	-
1218+55.00 TO 1226+95.00	840.0	39.0	3640.0	364.0	7.3	305.8	-	152.9	-	-	3640.0	-	-	56.7	-	-
1226+95.00 TO 1242+28.90	1533.9	51.0	8692.1	869.2	17.4	-	730.1	-	365.1	-	8692.1	-	-	103.5	-	-
72+19.10 TO 68+76.00	343.1	54.5	2077.7	207.8	4.2	-	174.5	-	87.3	-	2077.7	-	-	23.2	-	-
1383+92.00 TO 1387+00.00	308.0	69.0	2361.3	236.1	4.7	-	198.4	-	99.2	-	-	2361.3	-	-	132.0	-
1387+00.00 TO 1415+40.00	2840.0	60.0	18933.3	1893.3	37.9	-	1590.4	-	795.2	-	-	18933.3	-	-	918.2	-
1415+40.00 TO 1415+67.00	27.0	99.0	297.0	29.7	0.6	-	24.9	-	12.5	-	-	297.0	-	-	-	-
1415+67.00 TO 1416+16.00	49.0	145.0	789.4	78.9	1.6	-	66.3	-	33.2	-	-	789.4	-	-	-	118.1
1416+16.00 TO 1416+47.00	31.0	98.0	337.6	33.8	0.7	-	28.4	-	14.2	-	-	337.6	-	-	-	-
1416+47.00 TO 1418+04.00	157.0	60.0	1046.7	104.7	2.1	-	87.9	-	44.0	-	-	1053.3	-	-	87.1	83.3
1418+04.00 TO 1418+26.00	22.0	64.0	156.4	-	-	-	35.0	-	-	-	-	-	-	-	-	-
1418+26.00 TO 1418+47.00	21.0	60.0	140.0	14.7	0.3	-	11.8	-	5.9	-	-	146.7	-	-	-	166.7
TOTALS	26459	959	100640	10049	201	5528	2948	2764	1456	135	76578	23919	0	1553	1137	405

COLES/CUMBERLAND

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVING SCHEDULE COMBINED SECTION			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw\work\pwidot\swartzw\dms58699\shch_74157.dgn		DRAWN -	REVISED -		824	(16-2.19X-2)RS-1,19B,19BR		52	21			
PLOT SCALE = 50.0000' / 1"		CHECKED -	REVISED -		SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
PLOT DATE = 10/17/2008		DATE -	REVISED -					CONTRACT NO. 74157				