



**STAGE III NOTES**

SEE HIGHWAY STANDARD 701602-3, CASE II FOR SIGNS, ARROW BOARDS, SIGN LOCATIONS, AND NOTES NOT SHOWN ON THE STAGE III CONSTRUCTION PLAN SHEET.

FINAL SIGN LOCATION AND SPACING WILL BE DETERMINED BY THE ENGINEER TO FIT FIELD CONDITIONS.

**LEGEND**

- ○ DRUMS
- TEMPORARY CONCRETE BARRIER WALL (STANDARD 704001)
- IMPACT ATTENUATOR
- T TYPE III BARRICADE
- NO LEFT TURN SIGN (R3-2-2424)

• COLES/CUMBERLAND

FILE NAME =	c:\pwwork\pwwork\swartzw\des50699\sh...
USER NAME =	swartzw
DESIGNED -	
DRAWN -	stage3_74157.dgn
CHECKED -	
DATE -	
PLOT DATE =	10/17/2008

DESIGNED -	
DRAWN -	
CHECKED -	
DATE -	
PLOT DATE =	10/17/2008

DESIGNED -	
DRAWN -	
CHECKED -	
DATE -	
PLOT DATE =	10/17/2008

REVIS	
REVIS	
REVIS	
REVIS	
REVIS	

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**STAGE III CONSTRUCTION - SN 015-0025  
BRIDGE REPAIR OVER KICKAPOO CREEK**

SCALE: 20 SHEET NO. 3 OF 3 SHEETS STA. 1415+00 TO STA. 0+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
824	(16-2,19X-2)RS-1,19B,19BR	•	52	34
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 74157	