

EARTHWORK SCHEDULE						
STATION	TO	STATION	UNADJUSTED EXCAVATION (CU YD)	EXCAVATION ADJUSTED FOR SHINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
82+50.00	TO	82+75.00	6.0	4.5	8.7	-4.2
82+75.00	TO	83+00.00	25.9	19.4	10.3	9.1
83+00.00	TO	83+50.00	66.7	50.0	5.8	44.2
83+50.00	TO	84+00.00	40.4	30.3	6.6	23.7
84+00.00	TO	84+25.00	21.5	16.1	5.4	10.7
84+25.00	TO	84+43.50	10.9	8.2	2.6	5.6
85+97.50	TO	86+00.00	1.6	1.2	0.1	1.1
86+00.00	TO	86+50.00	46.5	34.9	1.8	33.1
86+50.00	TO	87+00.00	28.3	21.2	0	21.2
87+00.00	TO	87+50.00	34.7	26.0	0	26.0
87+50.00	TO	88+00.00	20.4	15.3	0	15.3
TOTAL =			302.9	227.1	41.3	185.8
ROUNDED TOTAL =			305	225	40	185

SEEDING CLASS 2 SCHEDULE							
STATION	TO	STATION	SEEDING CLASS 2 (ACRE)	MULCH METHOD 1 (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHOROUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)
82+50.00	TO	82+75.00	0.01	0.01	0.87	0.87	0.87
82+75.00	TO	83+00.00	0.02	0.02	2.24	2.24	2.24
83+00.00	TO	83+50.00	0.05	0.05	4.71	4.71	4.71
83+50.00	TO	84+00.00	0.07	0.07	6.22	6.22	6.22
84+00.00	TO	84+25.00	0.03	0.03	2.40	2.40	2.40
84+25.00	TO	84+43.50	0.00	0.00	0.21	0.21	0.21
84+43.50	TO	85+97.50	0.00	0.00	0.00	0.00	0.00
85+97.50	TO	86+00.00	0.00	0.00	0.00	0.00	0.00
86+00.00	TO	86+50.00	0.01	0.01	1.15	1.15	1.15
86+50.00	TO	87+00.00	0.01	0.01	1.17	1.17	1.17
87+00.00	TO	87+50.00	0.02	0.02	1.99	1.99	1.99
87+50.00	TO	88+00.00	0.02	0.02	1.38	1.38	1.38
TOTAL			0.25	0.25	22.4	22.4	22.4
ROUNDED TOTAL			0.25	0.25	25	25	25

GUARDRAIL SCHEDULE							
STATION	LT/RT OFFSET	GUARDRAIL REMOVAL (FEET)	SPBGR TYPE A (FEET)	TBT TY 6 (EACH)	TBT TY 1 (SPECIAL) (EACH)	GUARDRAIL MARKERS TYPE A (EACH)	TERMINAL MARKER DIRECT APPL. (EACH)
80+87.25	TO 81+37.25	RT			1	1	1
81+37.25	TO 83+99.75	RT	166.5	262.5		2	
83+99.75	TO 84+43.50	RT	53.5		1	1	
85+97.50	TO 86+41.25	RT			1	2	
86+41.25	TO 86+91.25	RT				2	1
82+90.00	TO 83+49.75	LT	53.4				
83+49.75	TO 83+99.75	LT	52.0		1	2	1
83+99.75	TO 84+43.50	LT	52.6		1	2	
85+97.50	TO 86+41.25	LT	53.5		1	1	
86+41.25	TO 89+16.25	LT	166.5	275.0		2	
89+16.25	TO 89+66.25	LT				1	1
TOTAL			598	538	4	4	16

PAVING SCHEDULE							
STATION	TO	STATION	BITUMINOUS BASE CSE WIDENING - 10" (SQ YDS)	AGGREGATE SHOULDER, TYPE B (TON)	PCC SLAB *(NMFP) (SQ YDS)	BRIDGE APPR. PAVT. CONNECTOR FLEXIBLE (SQ YDS)	BRIDGE APPROACH PAVEMENT (SQ YDS)
82+55.00	TO	83+92.50	137.5	21.4			
83+92.50	TO	84+07.50	15.0	2.3	15.0		
84+07.50	TO	84+13.50		0.9		21.3	
84+13.50	TO	84+43.50		4.7			106.7
85+97.50	TO	86+27.50		4.7			106.7
86+27.50	TO	86+33.50		0.9		21.3	
86+33.50	TO	87+75.00	141.5	22.0			
TOTAL			294.0	57.0	15.0	43.0	214.0

*NMFP= NOT MEASURED FOR PAYMENT, INCLUDED IN THE COST OF INLET TY B, STD 609006 (SEE INLET, TYPE B SCHEDULE)

INLET TYPE E, STANDARD 610001									
STATION	OFFSET LT/RT (FEET)	INLET, TY B STANDARD 610001 (EACH)	PIPE DRAINS-12" (FEET)	METAL END SECTION - 24" (EACH)	CONCRETE THRUST BOX (EACH)	HMA SHOULDER CURB (FEET)	STONE RIPRAP CLASS A3-8" (SQ YDS)	*STONE RIPRAP CLASS A1-4" (SQ YDS)	FILTER FABRIC (SQ YDS)
84+00	16.5' TO 52.3' LT	1	43.0	1	1	15	6	6	6
84+00	16.5' TO 49.3' RT	1	35.0	1	1	15	4	4	4
TOTAL		2	78.0	2	2	30	10	10	10

*STONE RIPRAP CLASS A1 USED AS BEDDING MATERIAL FOR STONE RIPRAP CLASS A3 (SEE DETAIL)

REMOVAL SCHEDULE					
STATION TO	STATION	REMOVING INLETS (EACH)	PAVEMENT REMOVAL (SQ YDS)	BITUMINOUS SHOULDER REMOVAL (SQ YDS)	
				LEFT	RIGHT
82+55.00	TO 83+92.50			15.3	15.3
83+92.50	TO 84+07.50		15.0	1.7	1.7
84+07.50	TO 84+46.50	3 @ STA. 84+39.98	104.0	4.3	4.3
85+93.50	TO 86+33.50		106.7	4.4	4.4
86+33.50	TO 87+75.00			15.7	15.7
TOTAL		3	226.0	84.0	

PAVEMENT MARKING SCHEDULE														
STATION			THERMOPLASTIC PAVEMENT MARKING LINE - 4" (FOOT)			POLYUREA PAVEMENT MARKING LINE - 4" (FOOT)			SHORT PAVEMENT MARKING (FOOT)	RAISED RELECTIVE PAVEMENT MARKERS (EACH)	RAISED RELECTIVE PAVT. MRKS. (BRIDGE) (EACH)	RAISED RELECTIVE PAVT. MRK. REMOVAL (EACH)	PAVEMENT MARKING REMOVAL (SQ FT)	WORK ZONE PAVEMENT MARKING REM. (SQ FT)
			SOLID WHITE	SKIP DASH YELLOW	SOLID YELLOW	SOLID WHITE	SKIP DASH YELLOW	SOLID YELLOW						
82+55.00	TO	83+47.00	184	23				9.2	1		1	52	2.3	
83+47.00	TO	84+13.50	133	17	67			6.7	1		1	54	1.7	
84+13.50	TO	86+27.50				428	54	214	21.4		3	174	5.4	
86+27.50	TO	87+75.00	295	37	148			14.8	2		2	120	3.7	
SUBTOTAL			612	77	214	428	54	214	52.0	4	3	400	13.0	
TOTAL			903			696			52.0	4	3	5	400	13.0

GUARDRAIL REMOVAL AND RE-ERECTION SCHEDULE			
STATION TO	STATION	REMOVE & RE-ERECT TBT-TY 6 (EACH)	REMOVE & REERECT SPBGR (FT)
83+62.525	TO 84+12.525		50
84+12.525	TO 84+46.90	1	
85+92.50	TO 86+26.875	1	
86+26.875	TO 86+76.875		50
TOTAL		2	100