



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 5, 2009

SUBJECT: FAS Route 779 (Pokey Road)  
Section 35RS-4  
Bond County  
Contract No. 76B99  
Item No. 25, January 16, 2009 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 1 of the Schedule of Prices.
2. Revised sheets 5 and 11 of the Fold-Up Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm  
Interim Bureau Chief  
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' with a small 'P.E.' to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Mary C. Lamie, Region 5, District 8; Mike Renner; Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

76B99

State Job # - C-98-065-08  
 PPS NBR - 0-00859-8014  
 County Name - BOND- -  
 Code - 5 - -  
 District - 8 - -  
 Section Number - 35RS-4

Project Number

Route  
 FAS 799

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X4421000	PARTIAL DEPTH PATCH	TON	22.000				
X4422025	PARTIAL DEPTH REM 2	SQ YD	186.000				
Z0017202	DOWEL BARS 1 1/2	EACH	62.000				
* DELETED							
* 40600200	BIT MATLS PR CT	TON	4.500				
40600300	AGG PR CT	TON	28.000				
40600635	LEV BIND MM N70	TON	535.000				
40600982	HMA SURF REM BUTT JT	SQ YD	475.000				
40600990	TEMPORARY RAMP	SQ YD	282.000				
40603085	HMA BC IL-19.0 N70	TON	101.000				
40603315	HMA SC "C" N70	TON	944.000				
44000198	HMA SURF REM VAR DP	SQ YD	891.000				
44003510	MEDIAN REMOVAL (PD)	SQ FT	993.000				
44200934	CL B PATCH T2 8	SQ YD	28.000				
44200942	CL B PATCH T3 8	SQ YD	24.000				
44200944	CL B PATCH T4 8	SQ YD	31.000				
* REVISED : DECEMBER 31, 2008							

# SUMMARY OF QUANTITIES

TOTAL SHEETS	SHEET NO.
18	5
CONTRACT NO.: 76899	

CODE NO	ITEM	UNIT	1000 100% STATE TOTAL QUANTITIES
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.5
40600300	AGGREGATE (PRIME COAT)	TON	28
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	535
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	475
40600990	TEMPORARY RAMP	SQ YD	282
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	101
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	944
44213100	PAVEMENT FABRIC	SQ YD	54
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	891
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	993
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	28
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	24
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	31
44213200	SAW CUTS	FOOT	242
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	107
48203100	HOT-MIX ASPHALT SHOULDERS	TON	399



## SUMMARY OF QUANTITIES

EAS 779  
SECTION 35RS-4  
BOND COUNTY

DATE TIME  
DATE TIME  
DATE TIME

1 Rev. 12-31-08

Rev.

PLOT DATE: DATE-TIME

DATE TIME  
 DATE TIME  
 DATE TIME

BITUMINOUS PAVING SCHEDULE

LOCATION	LEVEL BINDER (MM) NTO TON (1")	HMA SURF. CSE. MIX C NTO TON (1/2")	SO. YDS.	HMA SHOULDER TON	BIT. MATERIAL PRIME COAT TON	AGGREGATE PRIME COAT TON	AGGREGATE WEDGE SHOULDER TON	HMA BINDER CSE. IL-90 N-70 TON
STA. 11+02 TO 12+56 EOP RTE, 40 E. & W RADIUS AREAS/N/S LANES	45.4	68.00	810.7		0.25	1.62	0.00	0.00
EB OFF RAMP (ADDITIONAL)	0.00	19.90	236.4	0.00	0.07	0.50	0.00	(1 1/2") 19.90
STA. 12+50 TO 19+08 SB LANE TURN LANE								
STA. 12+54 TO 19+11 NB LANE	150.00	225.00	2678.9	0.00	0.84	4.30	0.00	0.00
STA. 22+28 TO 34+00 SB LANE	204.30	306.40	3647.80	0.00	1.14	7.30	0.00	0.00
STA. 22+48 TO 34+00 NB LANE								
STA. 22+30 TO 23+50 TURN LANE	30.80	46.30	550.6	0.00	0.17	1.10	0.00	0.00
STA. 26+10 TO 26+65 EXIT NB LANE								
FRONTAGE RD. LANE								
STA. 28+50 TO 29+50 TURN LANE	104.00	156.00	1858.80	0.00	0.58	3.60	0.00	0.00
STA. 34+00 TO 39+19								
SHOULDER AREA								
STA. 11+90 TO 19+04 NB/SB	0.00	0.00	3562.50	399.00	1.11	7.00	106.20	0.00
STA. 22+21 TO 39+19 NB/SB								
WB OFF RAMP (ADDITIONAL)	0.00	13.00	155.60	0.00	0.05	0.30	0.00	(1 1/2") 13.00
RAMP & STREET APPROACHES 2" AVERAGE X 10'	0.00	109.00	974.40	0.00	0.30	2.00	0.00	0.00
SB LANE STA. 13+50 TO 11+04 (VD)								(3") 67.80
TOTALS	534.50	943.60	14,475.70	399.00	4.5	27.72	106.20	100.70

TOTAL SHEETS	18
SHEET NO.	11
CONTRACT NO.: 76699	

Rev. 12-31-08

BITUMINOUS PAVING SCHEDULES

FAS 779 (POKEY RD.)  
 SECTION 35RS-4  
 BOND COUNTY

PLOT DATE TIME