

PAVEMENT MARKING SCHEDULE				
STATION	TO	STATION	L/R	PAINT WHITE LINE 4"
				FOOT
175+00.	TO	186+17.06	L	1117.06
186+17.06	TO	187+27.03	L	OTTERVILLE ROAD
187+27.03	TO	197+39.23	L	1012.2
175+00.	TO	186+37.06	R	1137.06
186+37.06	TO	187+30.56	R	MCCLUSKY ROAD
187+30.56	TO	197+39.23	L	1008.67
TOTAL:				4274.99

(QUANTITY INCLUDED FOR EDGELINE STRIPING ONLY)

SHOULDER SCHEDULE									
STATION	TO	STATION	L/R	LENGTH	RUMBLE STRIP	HMA SHOULDER 10"	PAVED SHOULDER REMOVAL	EARTH EXCAVATION	AGGREGATE SHOULDER WEDGE, TYPE B
				(FOOT)	(FOOT)	(SQYD)	(SQYD)	(CU YD)	(TON)
175+00.00	TO	186+17.06	L	1117.06	1117.06	372.35	124.12	91.40	41.37
186+17.06	TO	187+27.03	L	OTTERVILLE ROAD					
187+27.03	TO	197+39.23	L	1012.20	1012.20	337.40	112.47	82.82	37.49
175+00.00	TO	186+37.06	R	1137.06	1137.06	379.02	126.34	93.03	42.11
186+37.06	TO	187+30.56	R	MCCLUSKY ROAD					
187+30.56	TO	197+39.23	R	1008.67	1008.67	336.22	112.07	82.53	37.36
187+35.00	TO	187+55.00	R	20.00			6.67		
TOTAL:					4275	1425	482	350	159

ANY FILLS ON THE OUTSIDE OF THE SHOULDER WILL BE DONE WITH AGGREGATE WEDGE SHOULDER

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -					747	158,591	JERSEY	9	7
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	CONTRACT NO. 76C30			
	PLOT DATE = #DATE#	DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							