

PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	PREFORMED PAVEMENT MARKING				SHORT TERM	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS	WORK ZONE PAVEMENT MARKING REMOVAL
	LINE 6"	LINE 4"		LINE 8"	PAVEMENT MARKING			
	SKIP DASH WHITE	SOLID WHITE	SOLID YELLOW	SOLID WHITE	EDGE LINE DIAGONALS			
	FOOT	FOOT	FOOT	FOOT	FOOT			
NORTHBOUND						EACH	EACH	SO FT
7+20.0 TO 101+81.3	2365	9461	9461		757	118	118	252
101+81.3 TO 103+60.0	GAP FOR SN 028-0013 GUN CREEK BRIDGE							
103+60.0 TO 155+15.9	1289	5156	5156		412	64	64	137
155+15.9 TO 168+32.0	IL 154 INTERCHANGE SEE BELOW							
168+32.0 TO 186+05.0	443	1773	1773		142	22	22	47
186+05.0 TO 195+09.0	IL 154 INTERCHANGE SEE BELOW							
195+09.0 TO 303+14.0	2701	10805	10805		864	135	135	288
303+14.0 TO 304+79.0	GAP FOR SN 028-0012 MARCUM BRANCH BRIDGE							
304+79.0 TO 342+23.0	936	3744	3744		300	47	47	100
342+23.0 TO 355+18.0	REST AREA RAMPS SEE BELOW							
355+18.0 TO 370+11.0	373	1493	1493		119	19	19	40
370+11.0 TO 377+79.0	REST AREA RAMPS SEE BELOW							
377+79.0 TO 469+00	2280	9121	9121		730	114	114	243
IL 154 INTERCHANGE								
155+15.9 TO 168+32.0	329	1555	2225	104	181	87	87	60
186+05.0 TO 195+09.0	226	1124	1929		124	70	70	41
REST AREA RAMPS								
342+23.0 TO 355+18.0	324	2491	2582	108	141	58	58	47
370+11.0 TO 377+79.0	192	1169	1628		96	71	71	32
TOTALS	11,459	47,892	49,917	212	3,866	805	805	1,289
		97,810						

BRIDGE DECK SEALING

STRUCTURE NUMBER	DECK WIDTH (FEET)	DECK LENGTH (FEET)	APPROACH SHOULDER PAVEMENT LENGTH (FEET) (FEET)		APPROACH SHOULDER PAVEMENT WIDTH DRIVING (FEET) PASSING (FEET)		CONCRETE SEALER			BRIDGE DECK CONCRETE CRACK SEALER	SILICONE JOINT SEALER
							DECK AREA	APPROACH SHOULDER AREA	PARAPET TOP & FACE AREA	FOOT	FOOT
							SO FT	SO FT	SO FT		
028-0012	40.0	127.5	15.0	15.0	10.0	6.0	5100	480	1074	827	98
								6654			
028-0013	40.0	163.0	15.0	15.0	10.0	6.0	6520	480	1316	303	86
								8316			
TOTALS								14,970		1,130	184