

MEDIAN CROSSOVER SCHEDULE

LOCATION STATION	A	B	C	AREA SOFT	INCIDENTAL HMA SURFACING	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE SHOULDERS TYPE B, SPL	TEMPORARY RAMP	HMA SURFACE REMOVAL BUTT JOINT
	MIDDLE WIDTH (FEET)	NBEOS WIDTH (FEET)	SBEOS WIDTH (FEET)		TON	GAL	SO YD	SO YD	SO YD
20+00	23.60	56.50	56.30	1453.83	33	15	24	31	115
76+35	24.10	54.10	52.10	1442.74	33	14	24	29	110
215+69	18.50	54.20	56.50	1310.79	30	13	24	31	108
328+36	22.70	52.30	54.50	1419.86	32	14	24	30	112
456+16	22.00	45.50	45.90	941.74	21	9	24	26	98
TOTALS					148	66	122	147	543

GUARDRAIL SCHEDULE

LOCATION STATION TO STATION	GUARDRAIL REMOVAL FOOT	SPBGR TYPE A FOOT	TRAFFIC BARRIER TERMINAL					GUARDRAIL MARKERS		TERMINAL MARKERS DIRECT APPLIED EACH	REMARKS
			TY 1, SPL (TAN) EACH	TYPE 2 EACH	TYPE 5 EACH	TYPE 6 EACH	TYPE 6B EACH	AMBER EACH	SILVER EACH		
NORTHBOUND											
LT 9+96.00 TO 13+29.00	321.0	275.0	1				1		5	1	REMOVE AND REPLACE
LT 41+72.00 TO 57+51.00	1579.0	1514.0	1	1					9	1	REMOVE AND REPLACE
LT 67+49.00 TO 110+18.00	4083.0	4013.0	1	1	1	1			15	1	REMOVE AND REPLACE
RT 67+49.00 TO 110+18.00	138.0	375.0	1			1		7		1	REMOVE AND REPLACE
LT 123+72.00 TO 163+51.00	4004.0	3950.0	1	1					15	1	REMOVE AND REPLACE
LT 176+89.00 TO 179+34.00	265.0	275.0	1				1		5	1	REMOVE AND REPLACE
LT 229+51.00 TO 232+20.00	265.0	275.0	1				1		5	1	REMOVE AND REPLACE
LT 283+45.00 TO 286+10.00	265.0	275.0	1				1		5	1	REMOVE AND REPLACE
LT 296+70.00 TO 310+28.00	1216.0	1150.0	1	1	1	1			8	1	REMOVE AND REPLACE
RT 296+70.00 TO 310+28.00	198.0	375.0	1					7		1	REMOVE AND REPLACE
LT 415+74.00 TO 418+36.00	266.0	275.0	1				1		5	1	REMOVE AND REPLACE
LT 445+24.00 TO 448+00.00	277.0	275.0	1				1		5	1	REMOVE AND REPLACE
PROJECT TOTALS:	12877	13027	12	4	2	4	6	14	77	12	
									91		