

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
807	00-00374-01-PV	CHAMPAIGN	242	11
STA.		TO STA.		
ILLINOIS F.A. PROJ. NO. RS-HPP-1805(00)				
CONTRACT NO. 91368				

CODE NO.	ITEM	SAFETY CODE		2A	2A	1E	1E	1F	1F
		CONSTRUCTION CODE		J000	J000	Y030	Y030	Y031	Y031
		UNIT	TOTAL QUANTITY	ROADWAY CHAMPAIGN SECTION 80% FEDERAL 10% CITY 10% COUNTY	ROADWAY SAVOY SECTION 80% FEDERAL 10% VILLAGE 10% COUNTY	ROADWAY LIGHTING CHAMPAIGN SECTION 100% CITY	ROADWAY LIGHTING SAVOY SECTION 100% VILLAGE	TRAFFIC SIGNALS CHAMPAIGN SECTION 80% FEDERAL 10% CITY 10% COUNTY	TRAFFIC SIGNALS SAVOY SECTION 80% FEDERAL 10% VILLAGE 10% COUNTY
△*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	112				60	52
△*	88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	9				4	5
△*	88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	12				6	6
△*	88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	7				6	1
△*	88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	10				6	4
△*	88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	3					3
△*	88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	16				8	8
△	88200100	TRAFFIC SIGNAL BACKPLATE	EACH	22				12	10
△*	88500100	INDUCTIVE LOOP DETECTOR	EACH	6					6
△*	88600100	DETECTOR LOOP, TYPE I	FOOT	600					600
△*	88700200	LIGHT DETECTOR	EACH	4					4
△*	88700300	LIGHT DETECTOR AMPLIFIER	EACH	1					1
△*	88800100	PEDESTRIAN PUSH-BUTTON	EACH	6					6
△*	A2000320	TREE, ACER MIYABEI MORTON (STATE STREET MIYABE MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	14	14				
△*	A2004420	TREE, GINKGO BILOBA (GINKGO), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	7		7			
△*	A2006520	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	12		12			
△*	A2006720	TREE, QUERCUS MACROCARPA (BUR OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2		2			
△*	A2007120	TREE, QUERCUS RUBRA (RED OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	14	6	8			
△*	A2007920	TREE, TILIA AMERICANA REDMOND (REDMOND AMERICAN LINDEN), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	10	3	7			
△*	K0038000	PERENNIAL PLANTS, WETLAND EMERGENT TYPE	UNIT	34		34			
△*	K1004469	PERENNIAL PLANTS, PRAIRIE TYPE	UNIT	1		1			
△*	K1004572	PRAIRIE SEEDING (SPECIAL)	ACRE	0.3		0.3			
*	X0301232	SURVEY MARKER VAULT	EACH	3	1	2			
*	X0321905	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	496	27	469			
*	X0321906	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 15"	FOOT	13	13				
*	X0321907	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	23		23			
*	X0321909	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 24"	FOOT	65		65			
*	XX007744	CONCRETE ENCASEMENTS	EACH	3	1	2			
*	X0323093	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 24"	FOOT	28	28				
*	X0323954	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 18"	FOOT	12		12			
*	X0350810	BOLLARD REMOVAL	EACH	1		1			
*	X0932150	CURB AND GUTTER OUTLET, SPECIAL	EACH	2	2				
*	X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	20	3	17			
*	X6020125	RESTRICTED DEPTH INLET TYPE B, TYPE 3 FRAME AND GRATE	EACH	1		1			
*	X6020127	RESTRICTED DEPTH INLET TYPE B, TYPE 3V FRAME AND GRATE	EACH	12	2	10			

\*SEE SPECIAL PROVISIONS  
 △ SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

DATE : 10-08  
 DRAWN BY : J.L.B.  
 CHECKED BY : R.L.H.

SCALE : NONE