# SUMMARY OF QUANTITIES

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 807 | 00-00374-01-PV | CHAMPAIGN | 242 | 13 |
| STA. | | TO STA. | | |
| | ILLINOIS | F.A. PROJ. NO. RS-HPP-1805(001) | | |

CONTRACT NO. 91368

| | | SUMMARY OF QUANTITIES | SAFETY CODE | | 2A | 2A | 1E | 1E | 1F | 1F |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | CONSTRUCTION CODE | | J000 | J000 | Y030 | Y030 | Y031 | Y031 |
| | CODE NO. | ITEM | UNIT | TOTAL QUANTITY | ROADWAY CHAMPAIGN SECTION 80% FEDERAL 10% CITY 10% COUNTY | ROADWAY SAVOY SECTION 80% FEDERAL 10% VILLAGE 10% COUNTY | ROADWAY LIGHTING CHAMPAIGN SECTION 100% CITY | ROADWAY LIGHTING SAVOY SECTION 100% VILLAGE | TRAFFIC SIGNALS CHAMPAIGN SECTION 80% FEDERAL 10% CITY 10% COUNTY | TRAFFIC SIGNALS SAVOY SECTION 80% FEDERAL 10% VILLAGE 10% COUNTY |
| Δ * | XX007737 | JUNCTION BOX, SPECIAL (13"W× 24L×12"D) | EACH | 7 | | | 4 | 3 | | |
| Δ * | XX007738 | LIGHT POLE, ALUMINUM, 35 FT. M.H., 2-8 FT. MAST ARMS | EACH | 9 | | | | 9 | | |
| Δ * | XX007487 | LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT, SPECIAL | EACH | 45 | | | 45 | | | |
| Δ * | XX007743 | ROADWAY LIGHTING CONDUIT REMOVAL | FOOT | 351 | | | 351 | | | |
| Δ * | XX007739 | WIRELESS VEHICLE DETECTION SYSTEM | EACH | 1 | | | | | 1 | |
| * | XX007740 | FLEXIBLE POST BARRICADES | EACH | 3 | | 3 | | | | |
| Δ * | XX007741 | TREE, CELTIS LAEVIGATA (SUGAR HACKBERRY), 2-1/2" CALIPER, BALLED AND BURLAPPED | EACH | 12 | | 12 | | | | |
| Δ * | XX007742 | TREE, ZELKOVA SERRATA (JAPANESE ZELKOVA), 2-1/2" CALIPER, BALLED AND BURLAPPED | EACH | 12 | 4 | 8 | | | | |

*SEE SPECIAL PROVISIONS

Δ SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE : NONE

DATE : 10-08
DRAWN BY : J.L.B.
CHECKED BY : R.L.H.

P:\C01401\Plans\sheets\summary.dgn
10/31/2008 10:28:46 AM