

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
807	00-00374-01-PV	CHAMPAIGN	242	16
STA.		TO STA.		
ILLINOIS F.A. PROJ. NO. RS-HPP-1805(00)				
CONTRACT NO. 91368				

**42400300**  
**PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH**

STATION	TO STATION	SQ FT	
<b>CHAMPAIGN SECTION</b>			
CURTIS RD., MATTIS AVE. & FREEDOM BLVD.			
61+00.00 LT.	63+00.00 LT.	1589.7	
61+00.00 RT.	63+00.00 LT.	1609.8	
84+26.19 LT.	493+31.00 LT.	890.8	
493+31.00 RT.	87+39.81 LT.	1038.1	
84+26.37 RT.	492+00.00 LT.	972.3	
492+00.00 RT.	87+40.25 RT.	1112.8	
95+50.00 RT.	699+44.50 LT.	559.6	
699+44.50 RT.	98+96.20 RT.	962.1	
<b>SAVOY SECTION</b>			
CURTIS RD., PROSPECT AVE., WESLEY AVE. & REGENCY DR.			
131+91.04 LT.	662+00.00 LT.	7943.9	
658+50.00 RT.	800+78.10 LT.	7646.2	
649+83.50 RT.	799+25.50 LT.	10933.8	
799+56.00 RT.	146+98.70 RT.	243.0	
WESLEY AVENUE C.E.		88.0	
		<b>TOTAL</b>	<b>35590</b>

**42400800**  
**DETECTABLE WARNINGS**

LOCATION	SQ FT		
<b>CHAMPAIGN SECTION</b>			
CURTIS ROAD/MATTIS AVENUE			
85+26.72 LT.	21.7		
493+31.00 LT.	18.9		
493+31.00 RT.	18.0		
86+31.96 LT.	21.5		
85+29.40 RT.	21.9		
492+00.00 LT.	18.1		
492+00.00 RT.	18.7		
86+33.93 RT.	21.3		
CURTIS ROAD/FREEDOM BOULEVARD			
699+44.50 LT.	13.2		
699+44.50 RT.	13.7		
<b>SAVOY SECTION</b>			
CURTIS ROAD/PROSPECT AVENUE			
137+94.00 LT.	18.3		
656+69.00 LT.	19.6		
656+69.00 RT.	18.8		
138+99.00 LT.	21.5		
138+99.00 RT.	16.0		
655+62.88 RT.	23.1		
CURTIS ROAD/REGENCY DRIVE			
146+09.00 LT.	10.5		
800+45.00 LT.	20.4		
CURTIS ROAD/WESLEY AVENUE			
146+09.00 RT.	10.5		
799+56.00 LT.	20.5		
799+56.00 RT.	10.1		
146+76.00 RT.	12.7		
		<b>TOTAL</b>	<b>389</b>

**44300200**  
**STRIP REFLECTIVE CRACK CONTROL TREATMENT**

STATION	TO STATION	FOOT	
<b>SAVOY SECTION</b>			
CURTIS ROAD			
139+83.2 LT. & RT.	146+31.2 LT. & RT.	2592	
146+31.2 LT. & RT.	152+65.0 LT. & RT.	1902	
		<b>TOTAL</b>	<b>4494</b>

**48101200**  
**AGGREGATE SHOULDERS, TYPE B**

STATION	TO STATION	TON	
<b>SAVOY SECTION (5" THICK)</b>			
PROSPECT AVENUE			
662+05.0 LT.	664+56.1 LT.	17.7	
664+79.2 LT.	665+11.5 LT.	2.3	
662+05.0 RT.	665+11.5 LT.	21.6	
		<b>TOTAL</b>	<b>42</b>

**48203017**  
**HOT-MIX ASPHALT SHOULDERS, 5"**

STATION	TO STATION	SQ YD	
<b>CHAMPAIGN SECTION</b>			
CURTIS ROAD			
63+00.0 LT.	71+61.0 LT.	1005.5	
72+85.0 LT.	84+65.5 LT.	1338.3	
87+01.0 LT.	98+96.2 LT.	1354.1	
63+00.0 RT.	75+43.0 RT.	1424.0	
76+33.0 RT.	84+65.5 RT.	943.5	
87+01.0 RT.	95+86.0 RT.	1003.1	
97+67.5 RT.	98+96.2 RT.	145.4	
<b>MATTIS AVENUE</b>			
483+55.0 LT.	490+90.0 LT.	553.1	
493+79.0 LT.	500+76.0 LT.	602.9	
483+55.0 RT.	491+50.0 RT.	608.2	
495+20.0 RT.	500+76.0 RT.	473.9	
<b>SAVOY SECTION</b>			
CURTIS ROAD			
98+96.2 LT.	111+67.0 LT.	1442.5	
112+57.0 LT.	124+83.0 LT.	1392.0	
125+73.0 LT.	131+91.0 LT.	720.3	
98+96.2 RT.	111+69.0 RT.	1443.0	
112+59.0 RT.	124+86.0 RT.	1390.8	
125+76.0 RT.	137+86.0 RT.	1374.3	
		<b>TOTAL</b>	<b>17215</b>

**48203029**  
**HOT-MIX ASPHALT SHOULDERS, 8"**

STATION	TO STATION	SQ YD	
<b>CHAMPAIGN SECTION</b>			
CURTIS ROAD			
71+61.0 LT.	72+85.0 LT.	140.7	
75+43.0 RT.	76+33.0 RT.	102.1	
<b>MATTIS AVENUE</b>			
494+36.0 RT.	495+20.0 RT.	76.6	
<b>SAVOY SECTION</b>			
CURTIS ROAD			
111+67.0 LT.	112+57.0 LT.	102.1	
124+83.0 LT.	125+73.0 LT.	102.7	
111+69.0 RT.	112+59.0 RT.	102.1	
124+86.0 RT.	125+76.0 RT.	101.5	
		<b>TOTAL</b>	<b>728</b>

**60100060**  
**CONCRETE HEADWALL FOR PIPE DRAINS**

LOCATION	EACH		
<b>CHAMPAIGN SECTION</b>			
CURTIS ROAD			
68+70.0 LT.	1		
68+70.0 RT.	1		
78+90.0 LT.	1		
78+90.0 RT.	1		
82+55.0 LT.	1		
82+55.0 RT.	1		
93+50.0 LT.	1		
93+50.0 RT.	1		
<b>SAVOY SECTION</b>			
CURTIS ROAD			
100+35.0 LT.	1		
100+35.0 RT.	1		
105+00.0 LT.	1		
105+00.0 RT.	1		
120+25.0 LT.	1		
120+25.0 RT.	1		
122+15.0 LT.	1		
122+15.0 RT.	1		
		<b>TOTAL</b>	<b>16</b>

**60108100**  
**PIPE UNDERDRAINS 4" (SPECIAL)**

STATION	TO STATION	FOOT	
<b>CHAMPAIGN SECTION</b>			
CURTIS ROAD			
63+76.4 LT.	68+70.0 LT.	550	
63+76.2 LT.	68+70.0 RT.	548	
75+38.5 RT.	82+55.0 LT.	820	
75+38.5 RT.	82+55.0 RT.	826	
88+96.0 RT.	93+50.0 LT.	509	
88+96.0 RT.	93+50.0 RT.	515	
<b>SAVOY SECTION</b>			
CURTIS ROAD			
100+35.0 LT.	108+92.5 LT.	968	
100+35.0 RT.	108+92.5 RT.	960	
115+29.0 RT.	122+19.0 LT.	780	
115+29.0 RT.	122+19.0 RT.	787	
128+79.0 RT.	130+96.0 LT.	217	
128+79.0 RT.	130+96.0 RT.	217	
131+04.0 LT.	135+50.0 LT.	459	
131+04.0 RT.	135+27.0 RT.	472	
		<b>TOTAL</b>	<b>8628</b>

**60600605**  
**CONCRETE, TYPE B**

STATION	TO STATION	FOOT	
<b>SAVOY SECTION</b>			
CURTIS ROAD			
142+79.0 RT.	142+94.1 RT.	30.3	
		<b>TOTAL</b>	<b>31</b>

**60602600**  
**CONCRETE GUTTER, TYPE A (MODIFIED)**

STATION	TO STATION	FOOT	
<b>SAVOY SECTION</b>			
CURTIS ROAD			
109+55.00 LT.	111+87.30 LT.	232.3	
110+85.00 RT.	111+89.35 RT.	104.4	
		<b>TOTAL</b>	<b>337</b>

**60603800**  
**COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12**

STATION	TO STATION	FOOT	
<b>CHAMPAIGN SECTION</b>			
CURTIS ROAD			
63+76.3 LT.	68+77.5 LT.	501.7	
63+75.6 LT.	68+77.5 RT.	502.8	
75+38.5 LT.	82+58.5 LT.	720.2	
75+38.5 RT.	82+58.5 RT.	720.2	
88+96.0 LT.	93+61.0 LT.	465.2	
88+96.0 RT.	93+61.0 RT.	465.2	
<b>SAVOY SECTION</b>			
CURTIS ROAD			
100+22.5 LT.	108+92.5 LT.	870.3	
100+22.5 RT.	108+92.5 RT.	870.2	
115+29.0 LT.	122+19.0 LT.	690.2	
115+29.0 RT.	122+19.0 RT.	690.2	
128+79.0 LT.	135+24.0 LT.	645.0	
128+79.0 RT.	135+24.0 RT.	645.6	
		<b>TOTAL</b>	<b>7787</b>

**60604400**  
**COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18**

STATION	TO STATION	FOOT	
<b>SAVOY SECTION</b>			
CURTIS ROAD			
142+78.4 RT.	142+78.3 RT.	10.0	
142+94.7 RT.	142+94.8 RT.	10.0	
WESLEY AVENUE C.E.		42.0	
		<b>TOTAL</b>	<b>62</b>

**60605000**  
**COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24**

STATION	TO STATION	FOOT	
<b>CHAMPAIGN SECTION</b>			
CURTIS RD., MATTIS AVE., FREEDOM BLVD.			
61+00.0 LT.	62+80.0 LT.	179.1	
61+00.0 RT.	62+80.0 RT.	180.9	
84+80.5 LT.	493+79.0 LT.	116.1	
493+79.0 RT.	86+86.0 LT.	130.3	
84+80.5 RT.	491+50.0 LT.	125.6	
491+50.0 RT.	86+86.0 RT.	124.6	
95+86.0 RT.	698+73.0 LT.	134.2	
698+96.5 RT.	98+30.0 RT.	173.9	
<b>SAVOY SECTION</b>			
CURTIS RD. & PROSPECT AVE.			
131+86.0 LT.	662+05.0 LT.	1178.4	
662+05.0 RT.	139+84.1 LT.	647.8	
137+81.0 RT.	665+44.6 LT.	66.6	
655+44.4 RT.	139+82.3 RT.	137.7	
146+75.1 LT.	146+84.9 LT.	10.0	
147+96.0 LT.	148+04.0 LT.	8.0	
		<b>TOTAL</b>	<b>3214</b>

**60605400**  
**COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)**

STATION	TO STATION	FOOT	
<b>SAVOY SECTION</b>			
CURTIS RD., REGENCY DR. & WESLEY AVE.			
139+84.1 LT.	800+60.9 LT.	661.5	
139+83.2 RT.	799+40.0 LT.	663.0	
799+40.0 RT.	152+65.0 RT.	628.9	
		<b>TOTAL</b>	<b>1954</b>

**60619600**  
**CONCRETE MEDIAN, TYPE SB-6.12**

STATION	TO STATION	SQ FT	
<b>CHAMPAIGN SECTION</b>			
CURTIS ROAD			
63+67.5 LT.	63+76.1 LT.	53.2	
68+77.5 LT. & RT.	71+62.5 LT.	1914.7	
72+83.5 RT.	75+38.5 LT. & RT.	1769.1	
82+58.5 LT. & RT.	85+20.0 LT.	1833.0	
86+41.0 RT.	88+96.0 LT. & RT.	1758.5	
93+61.0 LT. & RT.	96+16.5 LT.	1774.8	
97+37.5 RT.	98+96.2 RT.	949.1	
<b>SAVOY SECTION</b>			
CURTIS ROAD			
98+96.2 RT.	100+22.5 LT. & RT.	943.7	
108+92.5 LT. & RT.	111+53.0 LT.	1814.7	
112+74.0 RT.	115+29.0 LT. & RT.	1769.1	
122+19.0 LT. & RT.	124+69.0 LT.	1713.8	
125+90.0 RT.	128+79.0 LT. & RT.	1945.4	
135+24.0 LT. & RT.	137+86.0 LT.	1838.9	
		<b>TOTAL</b>	<b>20078</b>

**60620000**  
**CONCRETE MEDIAN, TYPE SB-6.24**

STATION	TO STATION	SQ FT	
<b>CHAMPAIGN SECTION</b>			
CURTIS ROAD			
84+65.5 LT.	84+80.5 LT.	79.5	
86+86.0 LT.	87+01.0 LT.	80.2	
84+65.5 RT.	84+80.5 RT.	79.9	
86+86.0 RT.	87+01.0 RT.	79.5	
		<b>TOTAL</b>	<b>319</b>

**66700095**  
**PERMANENT SURVEY MARKERS**

LOCATION	EACH		
<b>CHAMPAIGN SECTION</b>			
CURTIS ROAD			
85+81.46 RT.	1		
<b>SAVOY SECTION</b>			
CURTIS ROAD			
112+13.79 RT.	1		
138+46.53 LT.	1		
		<b>TOTAL</b>	<b>3</b>

**X0301232**  
**SURVEY MARKER VAULT**

LOCATION	EACH		
<b>CHAMPAIGN SECTION</b>			
CURTIS ROAD			
85+81.46 RT.	1		
<b>SAVOY SECTION</b>			
CURTIS ROAD			
112+13.79 RT.	1		
138+46.53 LT.	1		
		<b>TOTAL</b>	<b>3</b>

**X0322630**  
**CONCRETE ENCASEMENTS**

LOCATION	EACH		
<b>CHAMPAIGN SECTION</b>			
PHINNEY BRANCH CHANNEL			
1039+80 LT.	1		
<b>SAVOY SECTION</b>			
CURTIS ROAD			
138+40 RT.	1		
PROSPECT AVENUE			
650+63 RT.	1		
		<b>TOTAL</b>	<b>3</b>

**X0932150**  
**CURB AND GUTTER OUTLET, SPECIAL**

STATION	TO STATION	EACH	
<b>CHAMPAIGN SECTION</b>			
CURTIS ROAD			
62+80.0 LT.	63+00.0 LT.	1	
62+80.0 RT.	63+00.0 RT.	1	
		<b>TOTAL</b>	<b>2</b>

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
DATE : 10-08  
DRAWN BY : J.L.B.  
CHECKED BY : R.L.H.  
SCALE : NONE