

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
807	00-00374-01-PV	CHAMPAIGN	242	17
STA.		TO STA.		
		ILLINOIS F.A. PROJ. NO. RS-HPP-1805(00)		
CONTRACT NO. 91368				

**Z0065900
SPECIAL DITCH CHECKS**

LOCATION	EACH
CHAMPAIGN SECTION	
CURTIS ROAD 88+92.5 RT.	1
SAVOY SECTION	
CURTIS ROAD 105+51.0 RT. 108+26.5 RT.	1 1
TOTAL	3

SALVAGED AGGREGATE MATERIAL 8"

LOCATION	50 YD
CHAMPAIGN SECTION	
TEMPORARY PAVEMENTS AT CURTIS ROAD AND MATTIS AVENUE INTERSECTION CONSTRUCTED DURING STAGE 3	350
TOTAL	350

NOTE : THIS MATERIAL MAY BE SUBSTITUTED FOR THE
AGGREGATE BASE COURSE, TYPE B MATERIAL WITH
THE APPROVAL OF THE ENGINEER.

SALVAGED AGGREGATE MATERIAL 12"

LOCATION	50 YD
CHAMPAIGN SECTION	
LOCATIONS APPROVED BY THE ENGINEER	3916
SAVOY SECTION	
LOCATIONS APPROVED BY THE ENGINEER	1329
TOTAL	5245

NOTE : THIS MATERIAL MAY BE SUBSTITUTED FOR THE
LIME MODIFIED SOIL 12" WITH THE APPROVAL
OF THE ENGINEER.

SALVAGED AGGREGATE MATERIAL 24"

LOCATION	50 YD
CHAMPAIGN SECTION	
LOCATIONS APPROVED BY THE ENGINEER	3359
SAVOY SECTION	
LOCATIONS APPROVED BY THE ENGINEER	3933
TOTAL	7292

NOTE : THIS MATERIAL MAY BE SUBSTITUTED FOR THE
LIME MODIFIED SOIL 24" WITH THE APPROVAL
OF THE ENGINEER.

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DATE : 10-08
DRAWN BY : J.L.B.
CHECKED BY : R.L.H.
SCALE : NONE