

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS				
LOCATION	LETTERS (SQ FT)	SYMBOLS (SQ FT)	TOTAL (SQ FT)	COMMENTS
CHAMPAIGN SECTION				
CURTIS ROAD				
63+06 RT.	4.9			"BIKE"
63+16 RT.	4.9			"LANE"
63+26 RT.		4.4		DIRECTIONAL ARROW
71+22.5 LT.		4.4		DIRECTIONAL ARROW
71+32.5 LT.	4.9			"LANE"
71+42.5 LT.	4.9			"BIKE"
73+03.5 RT.	4.9			"BIKE"
73+13.5 RT.	4.9			"LANE"
73+23.5 RT.		4.4		DIRECTIONAL ARROW
95+57 LT.		4.4		DIRECTIONAL ARROW
95+67 LT.	4.9			"LANE"
95+77 LT.	4.9			"BIKE"
SUBTOTAL CHAMPAIGN SECTION	39.2	17.6	56.8	
SAVOY SECTION				
CURTIS ROAD				
111+13 LT.		4.4		DIRECTIONAL ARROW
111+23 LT.	4.9			"LANE"
111+33 LT.	4.9			"BIKE"
112+94 RT.	4.9			"BIKE"
113+04 RT.	4.9			"LANE"
113+14 RT.		4.4		DIRECTIONAL ARROW
131+65 LT.		4.4		DIRECTIONAL ARROW
131+75 LT.	4.9			"LANE"
131+85 LT.	4.9			"BIKE"
143+11 C		31.2		DUAL LEFT TURN ARROW
144+06 C		15.6		LEFT TURN ARROW
144+86 RT.		11.5		THROUGH ARROW
144+86 RT.		15.6		RIGHT TURN ARROW
145+34.5 C		15.6		LEFT TURN ARROW
145+34.5 RT.		11.5		THROUGH ARROW
145+34.5 RT.		15.6		RIGHT TURN ARROW
145+83 C		15.6		LEFT TURN ARROW
145+83 RT.		11.5		THROUGH ARROW
145+83 RT.		15.6		RIGHT TURN ARROW
147+10 C		15.6		LEFT TURN ARROW
147+58.5 C		15.6		LEFT TURN ARROW
148+07 C		15.6		LEFT TURN ARROW
149+60 C		31.2		DUAL LEFT TURN ARROW
151+20 C		31.2		DUAL LEFT TURN ARROW
SUBTOTAL SAVOY SECTION	29.4	281.7	311.1	
TOTAL			367.9	

78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"		
LOCATION	CROSSWALK WHITE (FOOT)	TOTAL (FOOT)
SAVOY SECTION		
CURTIS ROAD		
146+06 TO 146+12 LT. & RT.	125	
146+71.8 TO 146+77.8 LT. & RT.	114	
WESLEY AVENUE		
799+52 TO 799+60 LT. & RT.	73	
REGENCY DRIVE		
800+41.9 TO 800+49.9 LT. & RT.	73	
SUBTOTAL SAVOY SECTION	385	385
TOTAL		385

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"			
LOCATION	DIAGONAL YELLOW (FOOT)	DIAGONAL WHITE (FOOT)	TOTAL (FOOT)
CHAMPAIGN SECTION			
MATTIS AVENUE			
483+85 TO 486+55 LT. & RT.	98		
SUBTOTAL CHAMPAIGN SECTION	98		98
SAVOY SECTION			
CURTIS ROAD			
139+83.2 TO 142+26 LT. & RT.	209		
146+60.8 LT. TO 152+65 LT.		235	
PROSPECT AVENUE			
662+00 TO 665+11.5 LT. & RT.	72	31	
SUBTOTAL SAVOY SECTION	281	266	547
TOTAL			645

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"		
LOCATION	STOP BAR WHITE (FOOT)	TOTAL (FOOT)
SAVOY SECTION		
WESLEY AVENUE		
799+48 RT.	16	
REGENCY DRIVE		
800+53.9 LT.	15	
SUBTOTAL SAVOY SECTION	31	31
TOTAL		31

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"							
LOCATION	SKIP-DASH YELLOW (FOOT)	SOLID YELLOW (FOOT)	DOUBLE YELLOW NARROW (FOOT)	SKIP-DASH WHITE (FOOT)	SOLID WHITE (FOOT)	LANE LINE EXTENSIONS WHITE (FOOT)	TOTAL (FOOT)
CHAMPAIGN SECTION							
CURTIS ROAD							
63+00 TO 84+65.5 LT. & RT.					4334		
87+01 TO 98+96.2 LT. & RT.					2219		
MATTIS AVENUE							
483+85 TO 486+55 LT. & RT.			1049		540		
499+76 TO 500+76 LT. & RT.			200		200		
SUBTOTAL CHAMPAIGN SECTION			1249		7293		8542
SAVOY SECTION							
CURTIS ROAD							
98+96.2 LT. TO 131+91 LT.					3296		
98+96.2 RT. TO 137+86 RT.					3889		
142+46 TO 143+76 LT. & RT.	80						
149+35 TO 152+65 LT. & RT.	180						
142+26 TO 144+06 LT. & RT.		360					
149+07 TO 152+65 LT. & RT.		716					
139+83.2 TO 142+26 LT. & RT.				971			
144+06 LT. TO 146+01 LT.				390			
146+92 RT. TO 149+07 RT.				430			
139+90 LT. TO 146+00 LT.				160			
139+90 RT. TO 140+40 RT.				20			
144+86 RT. TO 146+01 RT.					230		
146+60.8 LT. TO 152+65 LT.					724		
140+66 RT. TO 144+86 RT.						104	
PROSPECT AVENUE							
662+00 TO 665+11.5 LT. & RT.			1192		618		
SUBTOTAL SAVOY SECTION	260	1076		180	8757	104	13360
TOTAL							21902

ILLINOIS DEPARTMENT OF TRANSPORTATION
**PAVEMENT MARKING
SCHEDULE OF QUANTITIES**
DATE : 10-08
DRAWN BY : J.L.B.
CHECKED BY : R.L.H.
SCALE : NONE