CONTRACT NO. 94533

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

	CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% CITY	50% STATE 50% CITY
					F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)
					0+915.000 TO 2+756.900 AND 4+475.071 TO 15+545.000	2+756.900 TO 4+475.071	15+545.000 TO 16+016.000	2+756.900 TO 4+475.071	2+756.900 TO 4+475.071
					CONSTRUCTION CODE TYPE				
					1000-2A RURAL	1000-2A RURAL	1000-2A URBAN	SFTY-1B URBAN	SFTY-1B URBAN
**	A2001016	TREE, ACER RUBRUM (RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	40	30	5	5		
**	A2001316	TREE, ACER SACCHARINUM (SILVER MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	35	30	5			
**	A2006416	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	40	30	5	5		
**	A2006916	TREE, QUERCUS PALUSTRIS (PIN OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	40	30	5	5		
**	D2002288	EVERGREEN, PICEA PUNGENS GLAUCA(COLORADO BLUE SPRUCE), 8' HEIGHT, BALLED AND BURLAPPED	EACH	15			15		
	M2010110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	401	258	143			
	M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	903	610	293			
	M2010500	TREE REMOVAL, HECTARES	HA	0.6	0.6				
*	M2020010	EARTH EXCAVATION	CU M	73,555	68,953	2,188	2,414		
	M2020050	EARTH EXCAVATION (WIDENING)	CU M	3,465	3,338		127		
*	M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	680	680				
	M2080150	TRENCH BACKFILL	CU M	3423	165	3,253	5		
**	M2112500	TOPSOIL EXCAVATION AND PLACEMENT	CU M	24,185.4	23,434.0	9.7	741.7		
**	M2500200	SEEDING, CLASS 2	HA	19.2	18.6		0.6		
**	M2500400	NITROGEN FERTILIZER NUTRIENT	KG	1,980	1,853	70	57		
**	M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	1,980	1,853	70	57		
**	M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	1,980	1,853	70	57		
**	M2510115	MULCH, METHOD 2	HA	18.5	17.9		0.6		
**	M2510630	EROSION CONTROL BLANKET	SQ M	8,214	8,214				
**	M2520100	SODDING	SQ M	9815		9815			
**	M2520200	SUPPLEMENTAL WATERING	UNIT	736.2		736.2			
	M2800255	TEMPORARY EROSION CONTROL SEEDING	HA	19.2	18.6		0.6		
	M2800400	PERIMETER EROSION BARRIER	METER	1,275	1,275				
	M2800800	MULCH, METHOD 2	HA	19.2	18.6		0.6		
	M2810707	STONE DUMPED RIPRAP, CLASS A4	SQ M	4,811	4,575	190	46		
	M2820200	FILTER FABRIC	SQ M	5,357	5,121	190	46		
	M2830400	AGGREGATE DITCH	M TON	293	293				
	M3020456	PROCESSING MODIFIED SOIL 300MM	SQ M	7,712	7,712				
	M3021500	LIME	M TON	158.7	158.7				
	M3111100	SUB-BASE GRANULAR MATERIAL, TYPE B, 100MM	SQ M	14,151	7,712	6,439			
	M3511010	AGGREGATE BASE COURSE, TYPE B	M TON	1,862	1,582	86	193		
	M3530200	PORTLAND CEMENT CONCRETE BASE COURSE 200MM	SQ M	2,760		2,760			
	M3550500	HOT-MIX ASPHALT BASE COURSE, 200MM	SQ M	7,436	7,122		314		
	M3552100	HOT-MIX ASPHALT BASE COURSE, VARIABLE DEPTH	M TON	2,589	2,589				
	M4021010	AGGREGATE SURFACE COURSE, TYPE B	M TON	2,607	2,498	43	66		
*	M4021200	AGGREGATE FOR TEMPORARY ACCESS	M TON	1,764	1,144	584	36		
	M4060100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	107,937	94,601	10,533	2,803		
	M4060300	AGGREGATE (PRIME COAT)	M TON	374	317	45	12		
*	M4060895	CONSTRUCTING TEST STRIP	EACH	3	2	1			
	M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ M	884	716		168		
	M4060990	TEMPORARY RAMP	SQ M	89	72		17		
	M4062135	LEVELING BINDER (MACHINE METHOD), N70	M TON	7,854	6,209	1,396	249		
	M4063340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	M TON	6,984	5,246	1,373	365		
	M4075350	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 350MM	SQ M	31,381	31,381				
	M4080100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	23,137	19,770	1,981	1,386		
	M4080300	AGGREGATE (PRIME COAT)	M TON	12	11		1		
*	M4080500	INCIDENTAL HOT-MIX ASPHALT SURFACING	M TON	1,936	1,642	159	135		
	M4200200	PORTLAND CEMENT CONCRETE PAVEMENT 200MM	SQ M	2,252		2,252			
	M4205100	PAVEMENT FABRIC	SQ M	2,252		2,252			
	M4230150	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 150MM	SQ M	1,191	333	858			
	M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SQ M	4,087	1,758	2,329			
*	M4240100	PORTLAND CEMENT CONCRETE SIDEWALK 100MM	SQ M	3,293.5		1,493.5			1,800.0
*	M4245000	TEMPORARY SIDEWALK	SQ M	200		200			

* SEE SPECIAL PROVISIONS

** SPECIALTY ITEMS

CONTINUED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE | DRAWN BY KOJ

DATE OCTOBER 28, 2008 | CHECKED BY LWJ

H. M. & G. NO. 4420

PLOT DATE = 11/7/2008
FILE NAME = H:\4420\Final_Plans\D-ewings\D794533\SHT_004_sumq_V8.dgn