

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE							
				80% FED 20% STATE		80% FED 20% STATE		80% FED 20% STATE		100% CITY	50% STATE 50% CITY
				F.A.P. 781 (IL. RTE. 33)		F.A.P. 781 (IL. RTE. 33)		F.A.P. 781 (IL. RTE. 33)		F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)
				0+915.000 AND 4+475.071 TO 2+756.900 TO 15+545.000		2+756.900 TO 4+475.071		15+545.000 TO 16+016.000	2+756.900 TO 4+475.071	2+756.900 TO 4+475.071	
				I000-2A RURAL	I000-2A RURAL	I000-2A URBAN	SFTY-1B URBAN	SFTY-1B URBAN			
M542E120	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 450MM	EACH	8		6			2			
M542E128	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 600MM	EACH	16		14						
M542E136	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 750MM	EACH	4			2					
M542E144	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 900MM	EACH	6		6						
M542E148	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 1050MM	EACH	2								
M542E160	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 1500MM	EACH	2			2					
M542H420	PIPE CULVERTS, CLASS D, TYPE 1 300MM	METER	2.5		2.5						
M542H425	PIPE CULVERTS, CLASS D, TYPE 1 375MM	METER	924.5		908.0			16.5			
M542H430	PIPE CULVERTS, CLASS D, TYPE 1 450MM	METER	593.0		512.0			81.0			
M542H435	PIPE CULVERTS, CLASS D, TYPE 1 525MM	METER	93.5		93.5						
M542H440	PIPE CULVERTS, CLASS D, TYPE 1 600MM	METER	372.0		372.0						
M542H445	PIPE CULVERTS, CLASS D, TYPE 1 675MM	METER	37.0		37.0						
M542H450	PIPE CULVERTS, CLASS D, TYPE 1 750MM	METER	90.0		90.0						
M542H455	PIPE CULVERTS, CLASS D, TYPE 1 900MM	METER	76.0		76.0						
M542H460	PIPE CULVERTS, CLASS D, TYPE 1 1050MM	METER	24.5		24.5						
M542T220	PIPE CULVERTS, CLASS C, TYPE 1 375MM (TEMPORARY)	METER	58.0		58.0						
M542T225	PIPE CULVERTS, CLASS C, TYPE 1 450MM (TEMPORARY)	METER	6.1		6.1						
M542T235	PIPE CULVERTS, CLASS C, TYPE 1 600MM (TEMPORARY)	METER	6.1		6.1						
M5500030	STORM SEWERS, CLASS A, TYPE 1, 300MM	METER	705.1			705.1					
M5500050	STORM SEWERS, CLASS A, TYPE 1, 450MM	METER	242.3			242.3					
M5500065	STORM SEWERS, CLASS A, TYPE 1, 600MM	METER	760.9			760.9					
M5500075	STORM SEWERS, CLASS A, TYPE 1, 750MM	METER	180.1			180.1					
M5500085	STORM SEWERS, CLASS A, TYPE 1, 900MM	METER	319.8			319.8					
M5500095	STORM SEWERS, CLASS A, TYPE 1, 1050MM	METER	193.8			193.8					
M5500215	STORM SEWERS, CLASS B, TYPE 1, 150MM	METER	7.2			7.2					
M5510010	STORM SEWER REMOVAL 150MM	METER	18			18					
M5510025	STORM SEWER REMOVAL 300MM	METER	43			43					
M5510045	STORM SEWER REMOVAL 450MM	METER	194			194					
M5510055	STORM SEWER REMOVAL 525MM	METER	87			87					
M5510060	STORM SEWER REMOVAL 600MM	METER	365			365					
M5900200	EPOXY CRACK INJECTION	METER	5		5						
M5930100	CONTROLLED LOW-STRENGTH MATERIAL	CU M	7.0		7.0						
M6022110	RESTRICTED DEPTH MANHOLES, 1.2M DIAMETER TYPE 1 FRAME, CLOSED LID	EACH	9			9					
M6022115	RESTRICTED DEPTH MANHOLES, 1.2M DIAMETER TYPE 3 FRAME AND GRATE	EACH	2			2					
M6022210	RESTRICTED DEPTH MANHOLES, 1.5M DIAMETER TYPE 1 FRAME, CLOSED LID	EACH	17			17					
M6022215	RESTRICTED DEPTH MANHOLES, 1.5M DIAMETER TYPE 3 FRAME AND GRATE	EACH	1			1					
M6022310	RESTRICTED DEPTH MANHOLES, 1.8M DIAMETER TYPE 1 FRAME, CLOSED LID	EACH	10			10					
M6022315	RESTRICTED DEPTH MANHOLES, 1.8M DIAMETER TYPE 3 FRAME AND GRATE	EACH	5			5					
M6023255	MANHOLES, SPECIAL, 2.4M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1			1					
M6060070	CONCRETE CURB, TYPE B	METER	283.4			283.4					
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 15.30	METER	131.9			131.9					
M6060700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 15.60	METER	3,083.9			3,083.9					
M6300100	STEEL PLATE BEAM GUARD RAIL, TYPE A	METER	438.15		438.15						
M6320030	GUARDRAIL REMOVAL	METER	12		5			7			
M6690200	NON-SPECIAL WASTE DISPOSAL	CU M	291			291					
M7030100	SHORT-TERM PAVEMENT MARKING	METER	5,814		3,921			1704		189	
M7030620	TEMPORARY PAINT PAVEMENT MARKING LINE 100 MM	METER	33,577		32,091			426		1060	
M7040100	TEMPORARY CONCRETE BARRIER	METER	1,530		1,430					100	
M7040200	RELOCATE TEMPORARY CONCRETE BARRIER	METER	1,430		1,330					100	
M7800205	PAINT PAVEMENT MARKING-LINE 100 MM	METER	33,577		32,091			426		1060	
M7800215	PAINT PAVEMENT MARKING-LINE 150 MM	METER	106.8					106.8			
M7800240	PAINT PAVEMENT MARKING-LINE 600 MM	METER	15.6					15.6			
MX030199	TEMPORARY PAVEMENT	SQ M	3451		3451						
MX030203	TEMPORARY PAVEMENT REMOVAL	SQ M	3451		3451						

* SEE SPECIAL PROVISIONS
 ** SPECIALTY ITEMS

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p>SUMMARY OF QUANTITIES</p> <p>SCALE _____ DRAWN BY KOJ</p> <p>DATE OCTOBER 28, 2008 CHECKED BY LWJ</p>

PLOT DATE = 11/7/2008
 FILE NAME = H:\4420\1\end\Plans\Drawings\0794533\B1_004_aumg_V0.dgn

H. M. & G. NO. 4420