

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	45
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

RURAL ENTRANCE SCHEDULE - CONTINUED

LOCATION				WIDTH	LENGTH		RADIUS	AGGREGATE BASE COURSE, TYPE B	HOT-MIX ASPHALT BASE COURSE	AGGREGATE SURFACE COURSE, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)		AGGREGATE (PRIME COAT)	INCIDENTAL HOT-MIX ASPHALT SURFACING		PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT				
											PRIOR TO BINDER/BASE COURSE	PRIOR TO SURFACE COURSE		50MM	75MM	150 MM	200 MM			
STATION	LT/RT	TYPE	EXISTING MATERIAL	W1	L1	L2		150MM	200MM	150MM			M4080300	M4080500	M4230150	M4230200				
				METER	METER	METER	METER	M3511010	M3550500	M4021010	M4080100	LITER	LITER	M TON	M TON	M TON	M TON	SQ. M	SQ. M	
STA 14+763.300	RT	PE	BITUMINOUS	5.0	6.30	8.64	6	29.00												
STA 14+770.800	LT	PE	AGGREGATE	4.2	6.30	8.64	5 & 6	11.96		13.06			49.84						5.98	
STA 14+803.300	LT	PE	AGGREGATE	3.6	6.30	8.64	6	10.73		11.19			44.70						5.36	
STA 14+861.800	RT	PE	AGGREGATE	3.6	6.30	8.64	6	10.73		11.19			44.70						5.36	
STA 14+886.300	RT	PE	AGGREGATE	3.6	6.30	8.64	6	10.73		11.19			44.70						5.36	
STA 14+926.300	LT	PE	BITUMINOUS	3.6	6.30	8.64	6	21.92					91.34						10.96	
STA 14+926.300	RT	FE	DIRT	3.6	6.30	8.64	6					17.52								
STA 14+981.900	LT	PE	AGGREGATE	3.6	6.30	8.64	6	10.73		11.19			44.70						5.36	
STA 15+062.400	LT	ROAD	OIL & CHIP	See Plans	15.30	6.35	15		256.21		384.31	89.67	0.384	30.74						
STA 15+062.400	RT	ROAD	BITUMINOUS	See Plans	15.30	6.35	15		258.07		387.11	90.32	0.387	30.97						
STA 15+232.300	LT	CE	AGGREGATE	10.6	6.30	8.64	6		67.60	32.96	101.40	23.66	0.101	8.11						
STA 15+321.000	LT	CE	CONC/AGG	10.6	6.30	8.64	6												177.38	
STA 15+353.800	LT	CE	AGGREGATE	4.3	6.30	8.64	6		33.58	13.37	50.37	11.75	0.050	4.03						
STA 15+450.800	RT	PE	AGGREGATE	7.2	6.30	4.07	6	17.73		10.54					8.86					
STA 15+454.800	LT	CE	CONC/AGG	10.6	6.30	8.64	6			32.96									85.83	
STA 15+509.800	LT	CE	AGGREGATE	10.6	6.30	8.64	6			32.96									85.83	
STA 15+511.800	RT	PE	AGGREGATE	4.0	6.30	8.64	6	11.51		12.44		47.94			5.75					
<b>URBAN</b>																				
STA 15+595.800	LT	PE	AGGREGATE	7.2	6.30	8.64	6	17.73		22.39		73.86			8.86					
STA 15+660.800	LT	CE	BITUMINOUS	7.2	6.30	5.59	6		89.49		134.23	31.32	0.134	10.74						
STA 15+661.300	RT	ROAD	OIL & CHIP	5.8	9.30	2.60	9		109.19		163.78	38.21	0.164	13.10						
STA 15+723.100	RT	PE	BITUMINOUS	6.0	6.30	8.64	6	34.05				141.87			17.02					
STA 15+773.300	RT	ROAD	OIL & CHIP	5.9	9.30	2.35	9		114.80		172.20	40.18	0.172	13.78						
STA 15+870.300	RT	PE	AGGREGATE	3.6	6.30	8.64	6	10.73		11.19		44.70			5.36					
STA 15+871.400	LT	ROAD	AGGREGATE	3.6	9.30	2.59	9	20.45		3.36		85.21			10.22					
STA 15+890.000	LT	PE	AGGREGATE	3.6	6.30	22.41	6	10.73		29.04		44.70			5.36					
STA 15+916.600	RT	PE	BITUMINOUS	3.6	6.30	8.64	6	21.92				91.34			10.96					
STA 15+931.300	RT	PE	BITUMINOUS	3.6	6.30	8.64	6	21.92				91.34			10.96					
STA 15+960.300	LT	PE	BIT/AGGREGATE	10.3	6.30	8.64	6	55.78				232.41			27.89					
<b>TOTALS</b>								1,775.69	7,435.98	2,563.11	11,153.97	10,001.31	11.15	892.32	883.88	332.30	1,757.84			
TOTALS ROUNDED FOR SUMMARY SHEET								1,776	7,436	2,564	21,156		12	1,777	333	1,758				

PLOT DATE = 4/18/2008  
FILE NAME = H:\420\78042.ent-2.dgn

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center"><b>RURAL ENTRANCE SCHEDULE</b></p> <p>SCALE NO SCALE      DRAWN BY KOJ DATE APRIL 18, 2008      CHECKED BY RGH</p>