

**SUMMARY OF QUANTITIES**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	98	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 95500				

CODE NO.	ITEM	UNIT	URBAN - FAYETTE COUNTY					
			TOTAL QUANTITY	FEDERAL 80% CITY 20% TEA-21	FEDERAL 80% CITY 20% STU	CITY 100%	STATE 50% CITY 50%	STATE 100%
• 60226200	RESTRICTED DEPTH MANHOLES, 6' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7	1		6		
• 60226270	RESTRICTED DEPTH MANHOLES, 7' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2			2		
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	8	1		7		
• 60238500	INLETS, TYPE A, WITH SALVAGED FRAME AND GRATE	EACH	2			2		
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1			1		
60255500	MANHOLES TO BE ADJUSTED	EACH	11			11		
60500040	REMOVING MANHOLES	EACH	5	2		3		
60500050	REMOVING CATCH BASINS	EACH	23	12		11		
60500060	REMOVING INLETS	EACH	2	1		1		
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	3300	2978		322		
67100100	MOBILIZATION	L. SUM	1	0.85		0.05		0.1
70103816	TRAFFIC CONTROL SURVEILLANCE	CAL. MO.	13	11.05		0.65		1.3
• 70101700	TRAFFIC CONTROL AND PROTECTION	L. SUM	1	0.85		0.05		0.1
• 70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L. SUM	1	0.85		0.05		0.1
• 70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L. SUM	1	0.85		0.05		0.1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4819			1662	1435	1722
• 72000100	SIGN PANEL - TYPE 1	SQ. FT.	144	144				
• 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ. FT.	15	15				
• 72400720	RELOCATE SIGN PANEL - TYPE 2	SQ. FT.	10	10				
• 73400100	CONCRETE FOUNDATIONS	CU. YD.	8.7	8.7				
Δ 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ. FT.	188			32		156
Δ 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2646			370		2276
Δ 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	3023			867	990	1166
Δ 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	274			175		99
Δ 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1				
Δ 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	229	229				
Δ 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	1029	1029				
Δ 81013200	CONDUIT IN TRENCH, 6" DIA., PVC	FOOT	88	88				
Δ 81021370	CONDUIT PUSHED, 4" DIA., PVC	FOOT	283	283				
Δ • 81400100	HANDHOLE	EACH	4	2				2
Δ 83057130	LIGHT POLE, WOOD, 25 FOOT, CLASS 5	EACH	1			1		
Δ XX006965	UNIT DUCT, 600V, 5-1C NO. 4, 1/C NO. 4 GROUND, (XLP-TYPE USE), 2" DIA. POLYETHYLENE	FOOT	4286	4286				
Δ 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2886	2886				
Δ XX005099	LIGHTING CONTROLLER TYPE CB-RCS 200 AMP - 240 VOLT	EACH	1	1				
Δ 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	4	4				
Δ 84200700	LIGHTING FOUNDATION REMOVAL	EACH	4	4				
Δ • 87800110	CONCRETE FOUNDATION, TYPE A (SPECIAL)	FOOT	192	192				
Δ 88600100	DETECTOR LOOP, TYPE I	FOOT	867					867
• Z0050900	REMOVE CONCRETE FOUNDATION	EACH	2			2		
• XX000613	MODULAR BLOCK RETAINING WALL	SQ. FT.	705	705				

Δ SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_

DRAWN BY KOJ  
 CHECKED BY LWJ

CADD FILE: H:\4812\Des\gn\003-006sq\_4812.dgn  
 PLOTTED: 11/3/2008

H.M. & G. INC. 4812