F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	98	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 95500

STORM SEWER SCHEDULE

LOCATION	TRENCH BACKFILL, SPECIAL	• CLASS C PATCHES				• CLASS D PATCHES		STORM SEWER REMOVAL							REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	STORM SEWER																	
																		CLASS A															CLASS B JACKED IN PLACE		STEEL CASING BORED & JACKED	
																		TYPE 1					TYPE 2												
																					RUBBER GASKET								RUBBER GASKET					
		TYPE I 8 INCH	TYPE II 8 INCH	TYPE III 8 INCH	TYPE IV 8 INCH	TYPE III 15 INCH	TYPE IV 15 INCH	6″	8″	10″	12″	15″	18″	24″				12″	24″	30″		12″	12″	15″	18″	24″	30″	36″	42″	12″	24″	30″	36″	42″	48″
	CU. YD.	SQ. YD	SQ. YD	SQ. YD	SQ. YD	SQ. YD	SQ. YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
GALLATIN STREET																																			
LT. STA. 102+68 TO LT. STA. 2+85	15.0																							17											
LT. STA. 2+71.54, 72.11′																																			
RT. STA. 2+71.54 TO RT. STA. 2+75.12	3.7																					13													
RT. STA. 2+75.12, 57.06′																																			
RT. STA. 2+75.12 TO LT. STA. 2+85	54.0																													72					
LT. STA. 2+85, 17.50′																																			
LT. STA. 2+85 TO LT. STA. 3+44	40.8																							56											
LT. STA. 2+95, 23.0′	2.3																																		
LT. STA. 3+44, 18.50′																																			
LT. STA. 3+44 TO LT. STA. 4+19	23.8																							72											
RT. STA. 4+07, 20.53′																																			
RT. STA. 4+07 TO RT. STA. 4+22	2.1																	13																	
LT. STA. 4+19, 19.76′																																			
LT. STA. 4+19 TO RT. STA. 4+22	8.0																				37														
LT. STA. 4+19 TO LT. STA. 6+42.34	82.7													16					189																
RT. STA. 4+22, 20.28′																																			
LT. STA. 4+34, 24.10′	0.4																	2																	
LT. STA. 5+19, 25.53′	0.3																	2																	
RT. STA. 5+19, 27.64′																																			
RT. STA. 5+19 TO RT. STA. 5+34	1.7																	13																	
LT. STA. 5+33, 21.68′																																			
LT. STA. 5+33 TO RT. STA. 5+34	7.6																				48														
RT. STA. 5+34, 27.39′																																			
LT. STA. 5+86, 25.00′	9.1									16						1																			
LT. STA. 5+88, 26.70′	0.4																	2																	
LT. STA. 6+03, 26.95′	0.4																	2																	
RT. STA. 6+22, 15.91′																																			
RT. STA. 6+22 TO RT. STA. 6+43.19	13.7													16				18																	
RT. STA. 6+25.65, 21.13′	9.7									8				8		1																			
LT. STA. 6+42.34, 23.53′																																			
LT. STA. 6+42.34 TO LT. STA. 8+70	73.8																								211										
LT. STA. 6+42.34 TO RT. STA. 6+43.19	19.4																			47															
RT. STA. 6+43.19, 27.96′																																			
RT. STA. 6+43.19 TO RT. STA. 7+06	16.6																					57													
RT. STA. 6+74.47, 27.82′																																			
LT. STA. 6+98.2	0.6																																		
LT. STA. 7+05.45, 24.00′	7.3							16								1																			
LT. STA. 7+06, 27.83′	0.2																	2																	
RT. STA. 7+06, 27.83′																																			
RT. STA. 7+06 TO RT. STA. 7+21	1.7																	13																	
LT. STA. 7+21, 27.83′	0.2																	2																	
RT. STA. 7+21, 27.83′																																			
RT. STA. 7+22, 18.71′	7.3							16								1																			
LT. STA. 7+26.8	0.6																																		
RT. STA. 7+49.45, 23.86′	8.7								16						1																				
RT. STA. 8+58, 41.50′																																			
RT. STA. 8+58 TO RT. STA. 8+77	3.5																	22																	

FOR MORE ITEMS, SEE NEXT SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY KOJ

CHECKED BY LWJ

H.M. & G. NO. 4812

CADD FILE: H:\4812\Design\012-024sch_4812.dgn
PLOTTED: 11/3/2008