

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	98	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 95500				

**STORM SEWER SCHEDULE**

LOCATION	PIPE DRAINS (SPECIAL)	REINFORCED CONCRETE PIPE TEE					INLETS					MANHOLES								
		6"	RESTRICTED DEPTH					TRENCH DRAIN (2' x 8')	RESTRICTED DEPTH											
			12" PIPE	18" PIPE	24" PIPE	30" PIPE	36" PIPE		TYPE B	TYPE B	TYPE B	4' - DIA.	4' - DIA.	4' - DIA.	5' - DIA.	6' - DIA.	7' - DIA.			
			12" RISER	12" RISER	12" RISER	12" RISER	12" RISER		TYPE 3 F & G	TYPE 3V F & G	TYPE A SALVAGED F & G	TYPE B F & G	TYPE B F & G	TYPE B F & G	TYPE 1 F & CL	TYPE 1 F & CL	SALVAGED F & G	TYPE 1 F & CL	TYPE 1 F & CL	TYPE 1 F & CL
FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH		
RT. STA. 8+59.92, 39.54'																				
RT. STA. 8+60.53, 21.42'																				
LT. STA. 8+70, 23.75'																1				
LT. STA. 8+70 TO LT. STA. 8+77																				
LT. STA. 8+70 TO RT. STA. 8+77																				
LT. STA. 8+71.85, 22.82'																				
RT. STA. 8+73.29, 19.47'																				
LT. STA. 8+77, 27.83'																1				
LT. STA. 8+77 TO LT. STA. 8+92																				
RT. STA. 8+77, 27.83'																1				
RT. STA. 8+77 TO RT. STA. 8+92																				
LT. STA. 8+92, 27.83'										1										
RT. STA. 8+92, 27.83'										1										
LT. STA. 10+80, 23.75'																			1	
LT. STA. 10+80 TO LT. STA. 12+76																				
RT. STA. 10+80.2 TO RT. STA. 11+02																				
RT. STA. 10+85.30, 25.45'																				
LT. STA. 10+86.19, 26.71'																				
RT. STA. 10+97.6	13																			
LT. STA. 11+02, 27.83'				1						1										
RT. STA. 11+02, 27.83'																1				
RT. STA. 11+02 TO RT. STA. 11+17																				
LT. STA. 11+17, 27.83'				1						1										
RT. STA. 11+17, 27.83'										1										
LT. STA. 11+98.6	16																			
LT. STA. 12+76, 23.75'																			1	
LT. STA. 12+76 TO RT. STA. 12+76																				
LT. STA. 12+76 TO LT. STA. 14+92																				
LT. STA. 12+76, 27.83'																1				
RT. STA. 12+76 TO RT. STA. 12+91																				
LT. STA. 12+82, 27.83'				1						1										
RT. STA. 12+91, 27.83'										1										
LT. STA. 13+42.57, 28.78'																				
RT. STA. 14+80.71, 22.92'																				
LT. STA. 14+89.14, 29.97																				
LT. STA. 14+92, 23.75'																1				
LT. STA. 14+92 TO RT. STA. 14+92																				
LT. STA. 14+92 TO LT. STA. 18+19.95																				
RT. STA. 14+92, 27.83'																				
RT. STA. 14+92 TO RT. STA. 15+07																				
LT. STA. 15+03, 27.83'				1																
RT. STA. 15+07, 27.83'										1										
LT. STA. 15+18, 27.83'				1																
LT. STA. 16+00, 23.75'				1																
LT. STA. 16+00 TO RT. STA. 16+00																				
RT. STA. 16+00, 27.83'										1										

CADD FILE: H:\4812\05\10\012-024sch\_4812.dgn  
PLOTTED: 11/3/2008

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT.	HORIZ.	DRAWN BY KOJ
DATE	CHECKED BY LWJ	

H.M. & G. NO. 4812