F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	98	20
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 95500

STORM SEWER SCHEDULE

LOCATION	TRENCH BACKFILL, SPECIAL	* CLASS C PATCHES				* CLASS D PATCHES		STORM SEWER REMOVAL							REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	STORM SEWER																		
																		CLASS A																CLASS B JACKED IN PLACE		STEEL CASING BORED & JACKED	
																		TYPE 1					TYPE 2													
																						RUBBER GASKET									RUBBER GASKET				
		TYPE I 8 INCH	TYPE II 8 INCH	TYPE III 8 INCH	TYPE IV 8 INCH	TYPE III 15 INCH	TYPE IV 15 INCH	6"	8"	10"	12"	15"	18"	24"				12"	24"	30"	36"		12"	15"	18"	24"	30"	36"	42"	12"	24"	30"	36"	42"	48"
	CU. YD.	SQ. YD	SQ. YD	SQ. YD	SQ. YD	SQ. YD	SQ. YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
LT. STA. 507+17 TO LT. STA. 507+50	21.3							33										31																	
RT. STA. 507+17, 27.55′	1.7															1							5												
RT. STA. 507+40, 27.42′	1.8																						5												
LT. STA. 507+50, 27.58′																																			
LT. STA. 507+50 TO LT. STA. 507+65	17.1							15			8							13																	
LT. STA. 507+65, 27.55′																1																			
RT. STA. 507+65, 22.00′																																			
LT. STA. 507+65 TO RT. STA. 507+65	19.6			20.0																										46					
RT. STA. 507+65 TO RT. STA. 508+80	394.2										18			8	1																	110		110	
RT. STA. 508+80, 22.00′																																			
RT. STA. 508+80 TO RT. STA. 509+41	92.1				122.0									61													56								
RT. STA. 509+41, 22.00′																																			
RT. STA. 509+41 TO RT. STA. 510+10	90.4													69													64								
RT. STA. 510+10, 22.00′																																			
RT. STA. 510+10 TO RT. STA. 512+07	211.7						83.0							197														192							
RT. STA. 512+07, 22.00′																																			
RT. STA. 512+07 TO RT. STA. 513+72	98.7			19.0																								160							
RT. STA. 513+72, 23.82′																																			
RT. STA. 513+72 TO RT. STA. 515+70	55.8			16.0		19.0	78.0																					196							
TOTAL	4240	4	25	95	687	34	419	104	80	326	597	88	211	399	5	23	2	504	356	47	161	134	309	181	741	413	411	655	308	389	32	110	119	110	119

* See Plans for Exact Location

FOR MORE ITEMS, SEE NEXT SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY KOJ

CHECKED BY LWJ

H.M. & G. NO. 4812

CADD FILE: H:\4812\Design\012-024sch_4812.dgn
PLOTTED: 11/3/2008