F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	98	21
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 95500

STORM SEWER SCHEDULE

LOCATION	PIPE DRAINS (SPECIAL)	REINFORCED CONCRETE PIPE TEE					INLETS									MANHOLES					
												RESTRICTED DEPTH					RESTRICTED DEPTH				
		12" PIPE 12" RISER	18" PIPE 12" RISER	24" PIPE 12" RISER	30" PIPE 12" RISER	36" PIPE 12" RISER	TYPE A TYPE 3 F & G	TYPE A TYPE 3V F & G	TYPE A SALVAGED F & G	TYPE B TYPE 3 F & G	TYPE B TYPE 3V F & G	TYPE B TYPE 1 F & CL	TYPE B TYPE 3 F & G	TYPE B TYPE 3V F & G	TRENCH DRAIN (2' x 8')	4' - DIA. TYPE 1 F & CL	4' - DIA. TYPE 1 F & CL	4' - DIA. SALVAGED F & G	5' - DIA. TYPE 1 F & CL	6' - DIA. TYPE 1 F & CL	7' - DIA. TYPE 1 F & CL
	6" FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
LT. STA. 507+17 TO LT. STA. 507+50																					
RT. STA. 507+17, 27.55'					1						1										
RT. STA. 507+40, 27.42'					1								1								
LT. STA. 507+50, 27.58'													1								
LT. STA. 507+50 TO LT. STA. 507+65																					
LT. STA. 507+65, 27.55'													1								
RT. STA. 507+65, 22.00'																				1	
LT. STA. 507+65 TO RT. STA. 507+65																					
RT. STA. 507+65 TO RT. STA. 508+80																					
RT. STA. 508+80, 22.00'																				1	
RT. STA. 508+80 TO RT. STA. 509+41																					
RT. STA. 509+41, 22.00'																			1		
RT. STA. 509+41 TO RT. STA. 510+10																					
RT. STA. 510+10, 22.00'																			1		
RT. STA. 510+10 TO RT. STA. 512+07																					
RT. STA. 512+07, 22.00'																			1		
RT. STA. 512+07 TO RT. STA. 513+72																					
RT. STA. 513+72, 23.82'																			1		
RT. STA. 513+72 TO RT. STA. 515+70																					
TOTAL	76	1	7	18	3	6	8	30	2	1	9	1	7	11	1	2	6	1	9	7	2

* See Plans for Exact Location

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY KOJ

CHECKED BY LWJ

H.M. & G. NO. 4812

CADD FILE: H:\4812\Design\012-024sch_4812.dgn
PLOTTED: 11/3/2008