F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	98	24
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 95500

SIGN SCHEDULE

LOCATION		SIGN	SIZE	ORNAMENTAL SIGN OR FRAME	SIGN PANEL	RELOCATE SIGN PANEL		ORNAMENTAL STREET SIGN	ORNAMENTAL FRAME	ORNAMENTAL STREET SIGN POST, COMPLETE	CONCRETE FOUNDATION	COMMENTS
					TYPE 1	TYPE 1	TYPE 2					
STATION	LT / RT	CODE	IN X IN	MODEL	SQ. FT.	SQ. FT.	SQ. FT.	EACH	EACH	EACH	CU. YD.	
GALLATIN STREET												
2+75.1	RT	D6-X	24x30	RV2430		5.00			1	1	0.485	HISTORIC NATIONAL ROAD (RELOCATE)
		M6-1	21x15	RV2115	2.19				1			RIGHT ARROW
2+84.1	LT	D6-X	24x30	RV2430		5.00			1	1	0.485	HISTORIC NATIONAL ROAD (RELOCATE)
		M6-1	21x15	RV2115	2.19				1			LEFT ARROW
				S2-214				1				W GALLATIN ST / S SEVENTH ST
4+19.0	LT	R7-X	12x18	RV1218	1.50				1			NO PARKING ANYTIME
5+71.0	RT	R7-8	12x18	RV1218	1.50				1			HANDICAP RESERVED (LT ARROW)
5+79.0	LT	R7-X	12x18	RV1218	1.50				1			NO PARKING ANYTIME
6+23.5	LT	R1-1	30x30	030	6.25				1	1	0.485	STOP
				S2-214				1				W GALLATIN ST / S SIXTH ST
6+79.9	RT	R1-1	30x30	030	6.25				1	1	0.485	STOP
				S2-214				1				W GALLATIN ST / S SIXTH ST
7+04.2	RT	W3-1	36x36	D36	9.00				1	1	0.485	STOP AHEAD
7+36.0	RT	R7-108	12x18	RV1218	1.50				1			2 HOUR PARKING
8+16.0	LT	R7-108	12x18	RV1218	1.50				1			2 HOUR PARKING
8+16.0	RT	R7-8	12x18	RV1218	1.50				1			HANDICAP RESERVED (LT ARROW)
8+96.0	RT	R7-108	12x18	RV1218	1.50				1			2 HOUR PARKING
9+76.0	LT	R7-108	12x18	RV1218	1.50				1			2 HOUR PARKING
10+10.7	RT	R1-1	30x30	030	6.25				1	1	0.485	STOP
		R1-4	18x06		0.75				1			ALL WAY
10+26.3	LT	R1-1	30x30	030	6.25				1	1	0.485	STOP
		R1-4	18x06		0.75				1			ALL WAY
				S2-214				1				W GALLATIN ST / S FIFTH ST
10+87.8	RT	R1-1	30x30	030	6.25				1	1	0.485	STOP
		R1-4	18x06		0.75				1			ALL WAY
				S2-214				1				W GALLATIN ST / S FIFTH ST
11+04.1	LT	R1-1	30x30	030	6.25				1	1	0.485	STOP
		R1-4	18x06		0.75				1			ALL WAY
11+36.0	LT	R7-108	12x18	RV1218	1.50				1			2 HOUR PARKING (RT ARROW)
		R7-108	12x18	RV1218	1.50				1			15 MINUTE PARKING (LT ARROW)
11+36.0	RT	R7-108	12x18	RV1218	1.50				1			15 MINUTE PARKING (RT ARROW)
		R7-108	12x18	RV1218	1.50				1			2 HOUR PARKING (LT ARROW)
11+87.9	LT	I-8	24x24	S24	4.00				1	1	0.485	LIBRARY (SYMBOL)
		I-8P	24x12	RV2412	2.00				1			LIBRARY (WORD)
		M7-1	21x15	RV2115	2.19				1			LEFT ARROW
13+37.0	RT	R7-108	12x18	RV1218	1.50				1			2 HOUR PARKING
		W3-3	36x36	D36	9.00				1	1	0.485	SIGNAL AHEAD
13+91.8	LT	W3-1	36x36	D36	9.00				1	1		STOP AHEAD
		R7-108	12x18	RV1218	1.50				1			2 HOUR PARKING
14+23.3	LT	R1-1	30x30	030	6.25				1	1	0.485	STOP
				S2-214				1				W GALLATIN ST / S FOURTH ST
14+77.4	RT	R1-1	30x30	030	6.25				1	1	0.485	STOP
				S2-214				1				W GALLATIN ST / S FOURTH ST
15+10.0	RT	M2-1	21x15	RV2115	2.19				1	1	0.485	JCT
		M1-4	24x24	S24	4.00				1			40
		M1-4	24x24	S24	4.00				1			51
		M1-5	30x24	RV3024	5.00				1			185
15+36.0	LT	R7-108	12x18	RV1218	1.50				1			2 HOUR PARKING
15+36.0	RT	R7-108	12x18	RV1218	1.50				1			2 HOUR PARKING
16+16.0	LT	R7-108	12x18	RV1218	1.50				1			2 HOUR PARKING
17+27.5	RT	D1-3	48x30	RV4830			10.00		1	1	0.485	DIRECTIONAL
17+95.5	RT	D6-X	24x30	RV2430	5.00				1	1	0.485	HISTORIC NATIONAL ROAD (RELOCATE)
		M4-X	24x12	RV2412	2.00				1			SPUR
		M6-1	21x15	RV2115	2.19				1			ARROW RIGHT
17+76.0	LT	R7-108	12x18	RV1218	1.50				1	1	0.485	2 HOUR PARKING
18+04.6	LT	D6-X	24x30	RV2430		5.00			1	1	0.485	HISTORIC NATIONAL ROAD (RELOCATE)
				S2-214				1				W GALLATIN ST / KENNEDY BLVD
TOTAL					144	15.00	10.00	8	49	19	8.7	

PAVEMENT MARKINGS

LOCATION	TYPE	PAINT PAVEMENT MARKING				
		YELLOW		WHITE		
		LINE 4"	LINE 6"	LINE 6"	LINE 24"	LETTERS AND SYMBOLS
		FOOT	FOOT	FOOT	FOOT	SQ. FT.
GALLATIN STREET						
STA. 2+55 (STA 703+70 SEVENTH STREET) TO STA. 3+90	YELLOW - CENTERLINE - NO PASSING	366.0				
STA. 3+90 TO STA. 6+29	YELLOW - CENTERLINE - SKIP DASH	60.0				
	WHITE - PARKING STALLS			28.0		
	WHITE - CROSSWALK			118.0		
STA. 6+92.5 TO STA. 10+23.5	YELLOW - CENTERLINE - NO PASSING	614.0				
	WHITE - PARKING STALLS			176.0		
	WHITE - TURN LANE			100.0		
	WHITE - LARGE LEFT TURN ARROW					31.2
	WHITE - STOP BAR				33.0	
	WHITE - CROSSWALK			230.0		
STA. 10+90.5 TO STA. 14+22	YELLOW - CENTERLINE - NO PASSING	616.0				
	WHITE - PARKING STALLS			160.0		
	WHITE - TURN LANE			127.5		
	WHITE - LEFT TURN ARROW					62.4
	WHITE - STOP BAR				33.0	
	WHITE - CROSSWALK			230.0		
STA. 14+83 TO STA. 18+02.5	YELLOW - CENTERLINE - NO PASSING	620.0				
	WHITE - PARKING STALLS			176.0		
	YELLOW - NO PARKING		450.0			
	WHITE - TURN LANE			127.0		
	WHITE - LEFT TURN ARROW					62.4
	WHITE - STOP BAR				33.0	
	WHITE - CROSSWALK			233.0		
SIXTH STREET						
STA. 603+15 TO STA. 604+10	YELLOW - CENTERLINE - NO PASSING	162.0				
	WHITE - PARKING STALLS			28.0		
	WHITE - STOP BAR				21.0	
	WHITE - CROSSWALK			102.0		
STA. 604+71 TO STA. 605+32	YELLOW - CENTERLINE - NO PASSING	94.0				
	WHITE - PARKING STALLS			28.0		
	WHITE - TURN LANE			47.0		
	WHITE - LEFT TURN ARROW					15.6
	WHITE - STOP BAR				35.0	
	WHITE - CROSSWALK			129.0		
FIFTH STREET						
STA. 503+72 TO STA. 504+09	YELLOW - CENTERLINE - NO PASSING	46.0				
	WHITE - PARKING STALLS			12.0		
	WHITE - TURN LANE			23.0		
	WHITE - LEFT TURN ARROW					15.6
	WHITE - STOP BAR				33.0	
	WHITE - CROSSWALK			120.0		
STA. 504+72 TO STA. 504+98	YELLOW - CENTERLINE - NO PASSING	24.0				
	WHITE - PARKING STALLS			12.0		
	WHITE - TURN LANE			12.0		
	WHITE - STOP BAR				34.0	
	WHITE - CROSSWALK			122.0		
FOURTH STREET						
STA. 403+84.5 TO STA. 404+08	YELLOW - CENTERLINE - NO PASSING	19.0				
	WHITE - STOP BAR				23.0	
	WHITE - CROSSWALK			103.0		
STA. 404+71.5 TO STA. 404+98	YELLOW - CENTERLINE - NO PASSING	25.0				
	WHITE - STOP BAR				29.0	
	WHITE - CROSSWALK			129.0		
TOTALS		2646	450	2573	274	188
			3023			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY KOJ

CHECKED BY LWJ

H.M. & G. NO. 4812

CADD FILE: H:\4812\Design\012-024sch_4812.dgn
PLOTTED: 11/3/2008