

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00016-03-BR	MADISON	129	2
STA.		TO STA.		
CONTRACT NO.: 97351				

INDEX OF SHEETS

SHEET NO.	SHEET TITLE
1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	EXISTING & PROPOSED TYPICAL SECTIONS
5-8	SCHEDULE OF QUANTITIES
9-10	ALIGNMENT, TIES, AND BENCHMARKS
11-20	PLAN & PROFILE--WEST CORBIN STREET
21-26	GRADING PLAN--WEST CORBIN STREET
27	TRAFFIC CONTROL
28-33	EROSION AND SEDIMENT CONTROL PLANS--WEST CORBIN STREET
34-39	DRAINAGE AND UTILITIES PLAN--WEST CORBIN STREET
40-42	RIGHT-OF-WAY PLANS
43-44	PAVEMENT MARKING DETAILS
45	WETLAND PLANS
46-48	STORM SEWER PROFILES
49	SANITARY SEWER PROFILES
50-51	MISCELLANEOUS DETAILS
52-81	BRIDGE PLANS
82-83	CULVERT PLAN AND PROFILES
83-87	CULVERT DETAILS
88-129	CROSS SECTIONS--WEST CORBIN STREET

LIST OF ILLINOIS DOT HIGHWAY STANDARDS

STANDARD NO.	STANDARD TITLE
000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT REBARS
001006	DECIMAL OF AN INCH AND OF A FOOT
280001-04	TEMPORARY EROSION CONTROL SYSTEMS
420101-04	24' JOINTED PCC PAVEMENT
420401-07	BRIDGE APPROACH PAVEMENT
424001-05	CURB RAMPS FOR SIDEWALKS
515001-03	NAME PLATE FOR BRIDGES
542301-02	PRECAST REINFORCED CONCRETE FLARED END SECTION
542311-01	GRATING FOR CONCRETE FLARED END SECTION (FOR 600mm (24") THRU 1350mm (54") PIPE)
602301-02	INLET - TYPE A
602306-02	INLET - TYPE B
602401-02	MANHOLE TYPE A
602701-02	MANHOLE STEPS
604001-03	FRAME AND LIDS TYPE 1
604006-04	FRAME AND GRATE TYPE 3
604011-04	FRAME AND GRATE TYPE 3V
604036-02	GRATE TYPE 8
606001-04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
606101-04	TYPE A GUTTER (INLET, OUTLET & ENTRANCE)
609006-04	BRIDGE APPROACH PAVEMENT (DRAIN DETAIL)
630001-03	STEEL PLATE BEAM GUARDRAIL
631011-05	TRAFFIC BARRIER TERMINAL, TYPE 2
631032-04	TRAFFIC BARRIER TERMINAL, TYPE 6A
665001-02	WOVEN WIRE FENCE
701400-03	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-05	LANE CLOSURE, FREEWAY/EXPRESSWAY
701901-01	TRAFFIC CONTROL DEVICES
720001-01	SIGN PANEL MOUNTING DETAILS
720006-02	SIGN PANEL ERECTION DETAILS
720011-01	METAL POST FOR SIGNS, MARKERS & DELINEATORS
B.L.R. 10-6	PCC PAVEMENT SPECIAL
B.R.R. 21-3	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS

GENERAL NOTES

1. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
2. THE CONTRACTOR SHALL PROTECT UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE FOLLOWING UTILITIES ARE LOCATED WITHIN THE LIMITS OF THIS PROJECT:

AMEREN IP (GAS) 1050 WEST BLVD. BELLEVILLE, ILLINOIS 62221 (800) 755-5000	AMEREN IP (ELECTRIC) 1050 WEST BLVD. BELLEVILLE, ILLINOIS 62221 (800) 755-5000
VILLAGE OF BETHALTO (SEWER) 101 SOUTH PRAIRIE ST. BETHALTO, IL 62010 (618) 377-8723	AT&T (TELEPHONE) 203 GOETHE ST. COLLINSVILLE, ILLINOIS 62234 (618) 346-6490
VILLAGE OF BETHALTO (WATER) 101 SOUTH PRAIRIE ST. BETHALTO, IL 62010 (618) 377-8723	CHARTER COMMUNICATIONS (CABLE) 210 DIVISION ST. MARYVILLE, IL 62062 (888) 438-2427
J.U.L.I.E. 1-800-892-0123	

IT IS UNDERSTOOD AND AGREED THAT THE CONTRACTOR HAS TAKEN THE FOREGOING INTO CONSIDERATION IN SUBMITTING HIS BID, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR ANY DELAYS OR INCONVENIENCES CAUSED BY THE SAME.

THE INFORMATION AND DATA SHOWN OR INDICATED ON THESE IMPROVEMENT PLANS WITH RESPECT TO EXISTING UNDERGROUND FACILITIES AND UTILITIES AT OR CONTIGUOUS TO THE SITE IS BASED ON INFORMATION AND DATA FURNISHED BY THE OWNERS OF SUCH UNDERGROUND FACILITIES AND UTILITIES OR BY OTHERS. FIELD MARKINGS OF FACILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 96 HOURS ADVANCE NOTICE TO THE RESIDENT ENGINEER SO THAT UTILITIES CAN BE GIVEN NOTICE. NO GUARANTEE IS IMPLIED AS TO THE ACCURACY OR COMPLETENESS OF ANY SUCH INFORMATION OR DATA; AND CONTRACTOR SHALL HAVE FULL RESPONSIBILITY FOR (i) REVIEWING AND CHECKING ALL SUCH INFORMATION AND DATA, (ii) VERIFYING IF ANY CONFLICTS EXIST WITH THE PROPOSED WORKED AND UNDERGROUND FACILITIES AND UTILITIES SHOWN OR INDICATED ON THE IMPROVEMENT PLANS; (iii) COORDINATION OF THE WORK WITH THE OWNERS OF SUCH UNDERGROUND FACILITIES AND UTILITIES DURING CONSTRUCTION, AND (iv) THE SAFETY AND PROTECTION OF ALL SUCH UNDERGROUND FACILITIES AND UTILITIES AND REPAIR ANY DAMAGE THERETO RESULTING FROM THE WORK AT HIS EXPENSE.

3. ALL UTILITIES TO BE RELOCATED BY OTHERS.
4. THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.
5. ALL AREAS DISTURBED WITHIN OR BEYOND THE CONSTRUCTION LIMITS FOR ANY REASON SHALL BE SEEDED WITH CLASS 2 SEEDING, AS DIRECTED BY THE ENGINEER. NUTRIENTS SHALL CONFORM TO ARTICLE 250.04. FINAL SEEDING SHALL BE PERFORMED AS SOON AS POSSIBLE.
6. MULCH, AS APPLIED TO FINAL SEEDING (CLASS 2), SHALL CONFORM TO SECTION 251 OF THE STANDARD SPECIFICATIONS. MULCH UNLESS OTHERWISE PERMITTED BY THE ENGINEER, SHALL CONFORM TO METHOD 2 AS SPECIFIED IN ARTICLE 251.03 (b).
7. ALL WORK AS SHOWN ON THESE PLANS SHALL BE PERFORMED IN ACCORDANCE WITH THE SPECIAL PROVISIONS PREPARED BY HOELSCHER ENGINEERING, P.C. ENTITLED "FAU ROUTE 8959 (WEST CORBIN STREET) SECTION 05-00016-03-BR, CONTRACT NO. 97351, VILLAGE OF BETHALTO".
8. SEE STANDARD BLR-10 FOR DETAILS OF JOINTS AND REBARS NOT SHOWN ON THE PLANS.
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FOLLOWING THE REQUIREMENTS OF AN NPDES STORM WATER PERMIT FOR CONSTRUCTION ACTIVITY FOR THIS PROJECT.
11. TOPS OF INLETS WITH TYPE 3 AND TYPE 3V FRAME AND GRATE ARE TO THE EDGE OF PAVEMENT.
12. RIPRAP REMOVED ON SITE MAY BE REUSED IN THE PROJECT WITH THE APPROVAL OF THE ENGINEER.
13. THE CONTRACTOR SHALL VERIFY EXISTING SANITARY SEWER LOCATION AND ELEVATIONS PRIOR TO ORDERING OR INSTALLING MATERIALS. THE COST FOR THIS WORK SHALL BE INCLUDED IN THE PROPOSED SANITARY SEWER.
14. BORROW AREA HAS BEEN PROVIDED ON SITE. SEE WETLANDS PLAN FOR EXACT LOCATION.

ABBREVIATIONS AND SYMBOLS

TBR&R	TO BE REMOVED AND RE-ERECTED
REC	TO BE RECONSTRUCTED
TBADJ	TO BE ADJUSTED
TBA	TO BE ABANDONED

LEGEND:

⊕	EXISTING UTILITY POLE
⊙	EXISTING GUY WIRE
—ou—	EXISTING OVERHEAD UTILITY
—	CONSTRUCTION LIMITS
●	PROPOSED CURB INLET
⊙	PROPOSED STORM MANHOLE
●	PROPOSED SANITARY MANHOLE

DATE	2/7/06
BY	...
CHECKED	...
DATE	2/7/06
BY	...
NO.	...

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
INDEX OF SHEETS, HIGHWAY STANDARDS AND GENERAL NOTES
 FAU ROUTE 8959
 SECTION 05-00016-03-BR
 COUNTY MADISON
 DRAWN BY: R.A.W.