

SUMMARY OF QUANTITIES

PROP. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
793 8993	05-00025-00-TL 07-00025-01-WP	MADISON	135	4

CONTRACT NO. 97352

TO STA.

SUMMARY OF QUANTITIES			
CODE NO	ITEM	UNIT	QTY
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	172
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CA DA	40
70300100	SHORT TERM PAVEMENT MARKING	FOOT	756
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	24,078
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	250
72000100	SIGN PANEL - TYPE 1	SQ FT	42
73000100	WOOD SIGN SUPPORT	FOOT	86
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	631
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	25,370
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	362
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	222
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	518
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	155
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	252
* 78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	22
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	4,348
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	193
* 81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	90
* 81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	405
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	56
* 81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	21
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	10
* 81021340	CONDUIT PUSHED, 2 1/2", DIA., PVC	FOOT	104
* 81030100	CONDUIT SPLICE	EACH	2
* 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	5
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	572
* 81900300	TRENCH AND BACKFILL WITH SCREENINGS AND/OR SAND	FOOT	10
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,184
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	661
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3,158
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15
* 87900200	DRILL EXISTING HANDHOLE	EACH	3
* 88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2
* 88200300	TRAFFIC SIGNAL BACKPLATE, PLASTIC	EACH	2
* 88500520	INDUCTION LOOP DETECTOR AMPLIFIER WITH CALL DELAY AND CALL CARRY-OVER, DIGITAL DESIGN	EACH	7
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	1,601
* 89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	2

Y031-
IF

SUMMARY OF QUANTITIES			
CODE NO	ITEM	UNIT	QTY
* 89501300	RELOCATE EXISTING MAST ARM ASSEMBLY AND POLE	EACH	1
* 89502200	MODIFY EXISTING CONTROLLER	EACH	1
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	3,184
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1
* 89502380	REMOVE EXISTING HANDHOLE	EACH	4
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1
* 89502800	DISPOSITION OF SALVAGED TRAFFIC SIGNAL EQUIPMENT	L SUM	1
X7010010	TRAFFIC CONTROL - STAGE I	L SUM	1
X7010020	TRAFFIC CONTROL - STAGE II	L SUM	1
XX002053	LANDSCAPE RESTORATION	L SUM	1
XX002866	CONCRETE BARRIER WALL (SPECIAL)	CU YD	10
XX003503	FLARED END SECTION REMOVAL	EACH	7
XX001590	STORM SEWERS, PVC SDR 26, 15"	FOOT	284
Z0017100	DOWEL BARS	EACH	72
Z0041500	PLUG EXISTING CULVERTS	EACH	4
Z0075300	TIE BARS	EACH	72
XX001591	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36", SPECIAL	EACH	1
XX001592	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 42", SPECIAL	EACH	1

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

SUMMARY OF QUANTITIES

US 40 AND
TROY-O'FALLON ROAD IMPROVEMENTS
CITY OF TROY
MADISON COUNTY, ILLINOIS

P:\950162\DN\050162\SUMM01.dwg 4/17/2008 2:02:21 PM CDT

Y031-
IF