

PIP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
793 9392	05-00025-00-TL 07-00025-01-WR	MADISON	135	8
STA.		TO STA.		

CONTRACT NO. 97352

SIGNAGE SCHEDULE					
STATION	OFFSET (FEET)	SIGN TYPE	SIZE	SIGN PANEL -- TYPE 1 SQ. FT.	WOOD SIGN SUPPORT FOOT
MAST ARM MOUNTED					
SOUTHBOUND		R10-12	24"X30"	5.00	--
NORTHBOUND		R10-12	24"X30"	5.00	--
US 40					
241+91.88	37.33	RT	R3-1100	24"X24"	4.00
TROY-O'FALLON ROAD					
103+01.78	29.04	LT	R3-1100	24"X24"	4.00
104+22.69	29.67	RT	R3-9B	24"X36"	6.00
113+91.54	33.00	LT	R3-9B	24"X36"	6.00
118+54.25	33.00	RT	R3-9B	24"X36"	6.00
132+08.74	33.00	LT	R3-9B	24"X36"	6.00
				TOTAL	42
					85.5

RAISED REFLECTIVE PAVEMENT MARKER					
LOCATION		ONE-WAY CRYSTAL	ONE-WAY AMBER	TWO-WAY AMBER	
		EACH	EACH	EACH	
US 40					
236+99.46 TO 244+34.46			20	8	
241+39.46 TO 244+34.46		15			
245+57.64 TO 250+42.64		13			
245+57.64 TO 254+82.64			20	13	
SOUTH MAIN STREET					
96+37.11 TO 99+74.40			8		
98+54.40 TO 99+74.40		4			
TROY-O'FALLON ROAD					
100+61.83 TO 102+78.81		10			
124+01.66 TO 127+21.11		6			
100+61.83 TO 131+47.11			20	115	
		TOTAL	48	68	136

PAVEMENT MARKING REMOVAL			
STATION TO STATION	DESCRIPTION	PAVEMENT MARKING REMOVAL SQ FT	
SOUTH MAIN STREET			
96+37.11 TO 99+79.71	4" CENTERLINE	226.12	
96+63.54 TO 98+58.55 RT	4" SKIP-DASH	15.84	
98+58.55 TO 99+70.97 RT	4" TURN LANE	37.10	
98+79.88 TO 99+53.36 RT	LETTERS & SYMBOLS	84.60	
99+70.97 TO 99+79.93 RT	8" ENVELOPE	12.70	
99+78.20 TO 99+79.93 RT	12" DIAGONALS	2.46	
TROY-O'FALLON ROAD - STAGE 1			
100+63.80 TO 131+47.11 LT	4" CENTERLINE	2,037.36	
100+86.35 TO 107+62.80 RT	4" EDGE LINE	224.16	
101+18.24 TO 125+29.68 LT	4" EDGE LINE	788.90	
108+59.66 TO 125+19.80 RT	4" EDGE LINE	550.68	
125+83.17 TO 131+47.11 LT	4" EDGE LINE	188.92	
126+00.93 TO 131+47.11 RT	4" EDGE LINE	178.76	
		TOTAL	4,347.60

TEMPORARY PAINT PAVEMENT MARKING			
STATION	DESCRIPTION	4" YELLOW LINE	4" WHITE LINE
		FEET	FEET
TROY-O'FALLON ROAD - STAGE 1			
100+63.80 TO 131+47.11 LT	DOUBLE CENTERLINE	6,173.82	
100+86.35 TO 107+62.80 RT	EDGE LINE		679.28
101+18.24 TO 125+29.68 LT	EDGE LINE		2,390.60
108+59.66 TO 125+19.80 RT	EDGE LINE		1,668.73
125+83.17 TO 131+47.11 LT	EDGE LINE		572.49
126+00.93 TO 131+47.11 RT	EDGE LINE		541.71
TROY-O'FALLON ROAD - STAGE 2			
100+63.80 TO 131+47.11 RT	DOUBLE CENTERLINE	6,159.94	
100+86.35 TO 107+62.80 RT	EDGE LINE		680.21
100+91.94 TO 125+29.68 LT	EDGE LINE		2,428.43
108+59.66 TO 125+19.80 RT	EDGE LINE		1,676.52
125+83.17 TO 131+47.11 LT	EDGE LINE		568.53
126+00.93 TO 131+47.11 RT	EDGE LINE		537.73
		SUB-TOTAL	12,333.76
		TOTAL	24,077.99

THERMOPLASTIC PAVEMENT MARKINGS										
STATION	DESCRIPTION	4" YELLOW LINE	4" WHITE LINE	6" WHITE LINE	8" WHITE LINE	12" YELLOW LINE	12" WHITE LINE	24" WHITE LINE	LETTERS AND SYMBOLS	
		FEET	FEET	FEET	FEET	FEET	FEET	FEET	SQ FT	
US 40										
236+99.46 TO 244+34.46	DOUBLE CENTERLINE	2300.07								
236+99.46 TO 244+07.74 LT	EDGE LINE		665.59							
237+58.32 TO 244+37.81 RT	EDGE LINE		680.07							
237+48.83 TO 241+08.71	DIAGONALS					95.31				
239+71.89 TO 241+91.88 RT	2'-6" SKIP DASH		52.00							
241+39.46 TO 244+50.41 RT	LANE LINE		310.96							
241+87.57 TO 244+16.73	TURN ARROWS								93.6	
241+91.88 TO 244+52.49 RT	LANE LINE		260.62							
244+34.46	STOP BAR							11.00		
244+50.41 RT	STOP BAR							11.00		
244+52.49 TO 244+77.73	PAINTED MEDIAN				88.07		43.45			
244+65.43 RT	STOP BAR							18.00		
245+44.10 LT	STOP BAR							25.46		
245+44.10 TO 250+42.64 LT	LANE LINE		498.54							
245+52.22 TO 254+82.64 LT	EDGE LINE		872.28							
245+57.64	STOP BAR							11.00		
245+57.64 TO 254+82.64	DOUBLE CENTERLINE	2680.03								
246+03.79 TO 249+94.72	TURN ARROWS								46.8	
246+25.38 TO 254+82.64 RT	EDGE LINE		857.46							
250+88.39 TO 254+21.76	DIAGONALS					94.63				
SOUTH MAIN STREET										
96+37.11 TO 99+74.40	DOUBLE CENTERLINE	1052.20								
96+37.11 TO 99+97.04 LT	EDGE LINE		372.27							
96+93.18 TO 100+11.58 RT	EDGE LINE		363.60							
96+75.39 TO 98+36.10	DIAGONALS					35.84				
97+75.40 TO 98+54.40 RT	2'-6" SKIP DASH		20.00							
98+54.40 TO 99+91.83 RT	LANE LINE		137.43							
98+79.09 TO 99+63.00 RT	TURN ARROWS								84.6	
99+74.40 RT	STOP BAR							10.00		
99+91.83 RT	STOP BAR							26.03		
TROY-O'FALLON ROAD										
100+42.63 TO 100+80.55 LT	PAINTED MEDIAN				133.72		81.81			
100+43.79 TO 131+47.11 LT	EDGE LINE		3073.73							
100+56.36 LT	STOP BAR							18.00		
100+61.83 LT	STOP BAR							12.00		
100+61.83 TO 102+00.63	LANE LINE		138.80							
100+80.55 TO 102+78.81 LT	LANE LINE		198.26							
100+85.63 RT	STOP BAR							12.00		
100+85.63 TO 102+00.63 RT	DOUBLE CENTERLINE	230.00								
101+02.04 TO 126+99.37	TURN ARROWS								405.6	
102+00.63 TO 123+41.66 RT	TW TL		2141.03							
102+00.63 TO 123+41.66 RT	10'-30" SKIP DASH		540.00							
102+60.63 TO 123+41.66 LT	TW TL		2081.03							
102+60.63 TO 123+41.66 LT	10'-30" SKIP DASH		520.00							
102+78.81 TO 104+98.81	2'-6" SKIP DASH		54.00							
100+56.69 TO 131+47.11 RT	EDGE LINE		2924.08							
124+01.66 TO 125+16.66 RT	LANE LINE		115.00							
124+01.66 TO 125+16.66 LT	DOUBLE CENTERLINE	230.00								
126+06.11 TO 127+21.11 LT	LANE LINE		115.00							
126+06.11 TO 127+21.11 RT	DOUBLE CENTERLINE	230.00								
127+21.11 TO 131+47.11	DOUBLE CENTERLINE	1655.25								
127+21.11 TO 131+47.11	DIAGONALS					96.03				
TURTLE CREEK										
9+65.28 RT	STOP BAR							25.39		
9+69.28	CROSS WALK			60.93						
9+75.28	CROSS WALK			75.32						
MEADOWBROOKE DRIVE										
9+62.00 RT	STOP BAR							26.28		
9+66.00	CROSS WALK			57.83						
9+72.00	CROSS WALK			68.92						
FAIR OAKS DRIVE										
10+28.00	CROSS WALK			55.09						
10+34.00	CROSS WALK			44.00						
10+38.00 LT	STOP BAR							19.36		
		TOTAL	13,659.61	11,709.69	362.09	221.79	321.81	196.29	154.49	630.6

REVISIONS	
NAME	DATE

SCHEDULES

U.S. 40 TROY-O'FALLON ROAD IMPROVEMENTS
CITY OF TROY
MADISON COUNTY, ILLINOIS