

Location No.	5-01		
Structure No.	5 C 057 I074 L123.00		
County / Route	McLEAN CO. - I-74 WB - Carlock Weigh Station		
Scope of Work	This overhead cantilever is being replaced on a new drilled shaft foundation.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	0.50
72000300	SIGN PANEL - TYPE 3	SQFT	105.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	97.50
73301840	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	20.00
73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" X 7'-0")	FOOT	33.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	10.60
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00
The sign truss contractor is strongly encouraged to utilize a specialty foundation contractor for 73400200 Drilled Shaft Concrete Foundations due to the size and depth of the foundation and the soil conditions.			

Location No.	5-02		
Structure No.	5 C 057 I074 R122.20		
County / Route	McLEAN CO. - I-74 EB - Carlock Weigh Station		
Scope of Work	This overhead cantilever is being replaced on a new drilled shaft foundation.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	0.50
72000300	SIGN PANEL - TYPE 3	SQFT	105.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	97.50
73301840	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	20.00
73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" X 7'-0")	FOOT	33.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	10.60
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00
The sign truss contractor is strongly encouraged to utilize a specialty foundation contractor for 73400200 Drilled Shaft Concrete Foundations due to the size and depth of the foundation and the soil conditions.			

Location No.	5-03		
Structure No.	5 B 010 U136 L014.65		
County / Route	CHAMPAIGN CO. - US 136 WB under I-57 NB - Bridge 010-0013		
Scope of Work	This bridge mounted truss is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	0.50
72000300	SIGN PANEL - TYPE 3	SQFT	72.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	78.00
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	540.00
73400100	CONCRETE FOUNDATIONS	CUYD	1.40
73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	1.00

Location No.	5-04		
Structure No.	5 B 010 U136 R014.63		
County / Route	CHAMPAIGN CO. - US 136 EB under I-57 SB - Bridge 010-0012		
Scope of Work	This bridge mounted truss is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	0.50
72000300	SIGN PANEL - TYPE 3	SQFT	72.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	78.00
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	562.50
73400100	CONCRETE FOUNDATIONS	CUYD	1.40
73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	1.00