

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
				URBAN			80% FED 20% STATE	80% FED 13.3% STATE 6.7% VILLAGE OF PRAIRIE GROVE	100% CRYSTAL LAKE FIRE DEPT.
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004	T. S. SIGNAL 0021	EVP 0021			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1464	1464					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	218.4	218.4					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8867	8867					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	934	934					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	81	81					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	90	90					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	163	163					
* 72000100	SIGN PANEL - TYPE 1	SO FT	21.8		21.8				
* 72000200	SIGN PANEL - TYPE 2	SO FT	32	32					
* 72400310	REMOVE SIGN PANEL - TYPE 1	SO FT	24.2	24.2					
* 73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	1	1					

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
				URBAN			80% FED 20% STATE	80% FED 13.3% STATE 6.7% VILLAGE OF PRAIRIE GROVE	100% CRYSTAL LAKE FIRE DEPT.
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004	T. S. SIGNAL 0021	EVP 0021			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	218.4	218.4					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8867	8867					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	934	934					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	81	81					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	90	90					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	117	117					
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	6	6					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	95	95					
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1				
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	1701		1701				
* SPECIALTY ITEMS									

FILE NAME : c:\p\work\p14205\design\1114205-DE SIGN.dgn	USER NAME : dbrwn	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				IL. RTE. 176 AT SMITH ROAD SUMMARY OF QUANTITIES				F.A.P. RTE. 335	SECTION 146N-2	COUNTY MCHENRY	TOTAL SHEETS 65	SHEET NO. 5						
PLOT SCALE : 1/8" = 100'	CHECKED -	REVISED -	REVISED -									SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
PLOT DATE : 11/1/2013	DATE -	REVISED -	REVISED -																			
												CONTRACT NO. 60K20										