

● - DENOTES SPECIALTY ITEMS

△ - 0042 COST CODE

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES											
				ROADWAY	TRAFFIC SIGNALS US 12/20/45 JOLIET RD	TRAFFIC SIGNALS US 12/20/45 Q 63RD STREET	TRAFFIC SIGNALS US 12/20/45 COUNTRYSIDE	TRAFFIC SIGNALS JOLIET ROAD QUARRY	US 12/20/45 JOLIET RD PRE-EMPTION EQUIPMENT	TRAFFIC SIGNAL INTERCONNECT	LIGHTING	UTILITIES	UTILITIES	SIDEWALK	
				80% FED 20% STATE 0004	80% FED 10% STATE 10% COUNTRYSIDE 0021	80% FED 20% STATE 0021	80% FED 20% STATE 0021	80% FED 20% STATE 0021	100% COUNTRYSIDE 0021	80% FED 20% STATE 0021	100% COUNTRYSIDE 0021	100% COUNTRYSIDE 0043	100% S. LYONS TOWN SAN DISTRICT 0043	80% FED 20% COUNTRYSIDE 0021	
88700200	LIGHT DETECTOR	EACH	3							3					
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1							1					
88800100	PEDESTRIAN PUSH-BUTTON	EACH	6		6										
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	4		1	1	1	1							
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	5,478							5,478					
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1										
89502380	REMOVE EXISTING HANDHOLE	EACH	25		18					7					
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5		5										
Z0007510	ENGINEERED BARRIER	SO YD	400	400											
Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SO FT	216	216											
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1											
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	384	384											
Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1							1					
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	311	311											
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	4		1	1	1	1							
A2004820	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	22	22											
A2005020	TREE, GYMNOCLADUS DJOICUS (KENTUCKY COFFEETREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	8	8											
A2007920	TREE, TILIA AMERICANA REDMOND (REDMOND AMERICAN LINDEN), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	7	7											