

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FEDERAL 10% STATE WILL COUNTY 0021	90% FEDERAL 10% STATE COOK COUNTY 0021			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	936	936				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	254	254				
20200100	EARTH EXCAVATION	CU YD	3176	3176				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	6083	6083				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	7506	7506				
25000210	SEEDING, CLASS 2A	ACRE	1.6	1.6				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	145	145				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	145	145				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	145	145				
25100630	EROSION CONTROL BLANKET	SO YD	7505	7505				
31102100	SUBBASE GRANULAR MATERIAL, TYPE C 4"	SO YD	20232	20232				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4	3.5	0.5			
40600300	AGGREGATE (PRIME COAT)	TON	18	17	1			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	14	13	1			

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FEDERAL 10% STATE WILL COUNTY 0021	90% FEDERAL 10% STATE COOK COUNTY 0021			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1010	970	40			
42001300	PROTECTIVE COAT	SO YD	180	180				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	8984	8634	350			
44003100	MEDIAN REMOVAL	SO FT	1616	1616				
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	13498	13498				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	17995	17995				
60251200	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE B GRATE	EACH	3	3				
60624600	CORRUGATED MEDIAN	SO FT	1616	1616				
* 63000370	LONG-SPAN GUARDRAIL OVER CULVERT, 25 FT SPAN	FOOT	50	50				
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	16	12	4			
63200310	GUARDRAIL REMOVAL	FOOT	600	400	200			
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	45479	45479				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	5	1			

14

13

\*Specialty Items

FILE NAME: C:\p\work\10000001\10293497-012282-01-10000001.dwg	USER NAME: dcocker	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		NEW AVE. (COOK COUNTY LINE TO IL 171/ARCHER AVE.) SUMMARY OF QUANTITIES		F.A.U. RTE. 0361	SECTION 2011-223-1	COUNTY COOK & WILL	TOTAL SHEETS 90	SHEET NO. 3
PLOT SCALE: 1/8" = 1'-0"		CHECKED: -	REVISED: -	SCALE: SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 60R86		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
PLOT DATE: 10/31/2003		DATE: -	REVISED: -									