

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED. 10% ST. ROADWAY 0004	90% FED. 10% ST. TRAFFIC SIGNAL 0021	90% FED. 10% ST. TRAFFIC SIGNAL INTER-CONNECT 0021	100% VILLAGE CHICAGO HEIGHTS E.V.P 0021	80% ST. 20% VILL. CHICAGO HEIGHTS SIDEWALK 0021	80% ST. 20% VILL. OLYMPIA FIELDS SIDEWALK 0021
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	12	12					
20101100	TREE TRUNK PROTECTION	EACH	4	4					
20200100	EARTH EXCAVATION	CU YD	121	121					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	219	219					
20800150	TRENCH BACKFILL	CU YD	60	60					
21101625	TOPSOIL FURNISH AND PLACE, 6"	SO YD	1245	1245					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	71	71					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	71	71					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	71	71					
25200110	SODDING, SALT TOLERANT	SO YD	1245	1245					
25200200	SUPPLEMENTAL WATERING	UNIT	13	13					
28000400	PERIMETER EROSION BARRIER	FOOT	975	975					
28000510	INLET FILTERS	EACH	27	27					
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	646	646					
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SO YD	726	726					

• SPECIALTY ITEMS

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED. 10% ST. ROADWAY 0004	90% FED. 10% ST. TRAFFIC SIGNAL 0021	90% FED. 10% ST. TRAFFIC SIGNAL INTER-CONNECT 0021	100% VILLAGE CHICAGO HEIGHTS E.V.P 0021	80% ST. 20% VILL. CHICAGO HEIGHTS SIDEWALK 0021	80% ST. 20% VILL. OLYMPIA FIELDS SIDEWALK 0021
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	486	486					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5	0.5					
40600300	AGGREGATE (PRIME COAT)	TON	1	1					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	54	54					
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	646	646					
42001300	PROTECTIVE COAT	SO YD	3086	3086					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	213	213					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	2583					2233	350
42400800	DETECTABLE WARNINGS	SO FT	510	510					
44000100	PAVEMENT REMOVAL	SO YD	544	544					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	685	685					
44000300	CURB REMOVAL	FOOT	381	381					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2299	2299					
44000600	SIDEWALK REMOVAL	SO FT	76	76					

• SPECIALTY ITEMS

FILE NAME: c:\pr-work\p102812\jlmenez\102812-02812-02812.dwg
 USER NAME: jlmenez
 PLOT SCALE: 1/8" = 1'-0"
 PLOT DATE: 10/21/2013

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE. 353 SECTION 23N-2 COUNTY COOK TOTAL SHEETS 75 SHEET NO. 4 CONTRACT NO. 60T19
 FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT