

URBAN

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		90% FED. 10% ST. ROADWAY 0004	90% FED. 10% ST. TRAFFIC SIGNAL 0021	90% FED. 10% ST. TRAFFIC SIGNAL INTER-CONNECT 0021	100% VILLAGE CHICAGO HEIGHTS E.V.P 0021	80% ST. 20% VILL. CHICAGO HEIGHTS SIDEWALK 0021	80% ST. 20% VILL. OLYMPIA FIELDS SIDEWALK 0021
•81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	57	57					
•81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	134	134					
•81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	717	717					
•81400100	HANDHOLE	EACH	1	1					
•81400200	HEAVY-DUTY HANDHOLE	EACH	4	4					
•81400300	DOUBLE HANDHOLE	EACH	3	3					
•85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3		3				
•86400100	TRANSCEIVER - FIBER OPTIC	EACH	1	1					
•87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	4251	4251					
•87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1516	1516					
•87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2336	2336					
•87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3704	3704					

• SPECIALTY ITEMS

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		90% FED. 10% ST. ROADWAY 0004	90% FED. 10% ST. TRAFFIC SIGNAL 0021	90% FED. 10% ST. TRAFFIC SIGNAL INTER-CONNECT 0021	100% VILLAGE CHICAGO HEIGHTS E.V.P 0021	80% ST. 20% VILL. CHICAGO HEIGHTS SIDEWALK 0021	80% ST. 20% VILL. OLYMPIA FIELDS SIDEWALK 0021
•87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	903	903					
•87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	6430	6430					
•87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	149	149					
•87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1181	1181					
•87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	3	3					
•87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2	2					
•87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2	2					
•87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1	1					
•87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1	1					
•87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1	1					

• SPECIALTY ITEMS

FILE NAME : c:\pwworkspace\jlmenez\1\102812.dwg	USER NAME : jlmenezjl	DESIGNED -	REVISED -
PLOT SCALE : 100,0000 1" = 100'		DRAWN -	REVISED -
PLOT DATE : 10/21/2013		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	

F.A. RTE. 353	SECTION 23N-2	COUNTY COOK	TOTAL SHEETS 75	SHEET NO. 7
CONTRACT NO. 60T19				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				