



**SCHEDULE OF QUANTITIES**

QUANTITY	UNIT	ITEM
123	FOOT	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA
1	EACH	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION
751	FOOT	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C
1	EACH	DRILL EXISTING HANDHOLE
1528	FOOT	REMOVE ELECTRIC CABLE FROM CONDUIT
777	FOOT	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F
1	EACH	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "EAGLE" TO MATCH THE EXISTING ADJACENT SYSTEM.

J:\13003\06\N\CADD\_Sheets\0571-sht-ts-27.dgn 08-JAN-2014 15:58 TIME



USER NAME	• mgorvide	DESIGNED	- MG	REVISED	▲ - ADDENDUM 1 01/08/14
PLLOT SCALE	• 48.000000/1.000000	DRAWN	- MG	REVISED	-
PLLOT DATE	• 08-JAN-2014 15:56	CHECKED	- KGP	REVISED	-
		DATE	- 10/25/2013	REVISED	-

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEMATIC DIAGRAM  
ILLINOIS ROUTE 64 (VILLA AVE. TO BERTEAU AVE.)

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	131B-BR	DUPAGE	111	68
			CONTRACT NO. 60V24	
ILLINOIS FED. AID PROJECT				

SCALE: AS NOTED | SHEET NO. 25 OF 26 SHEETS | STA. TO STA.