

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				80% FEDERAL / 20% STATE		TRAFFIC SIGNALS		ROADWAY LIGHTING / EVP		SIDEWALK		
				ROADWAY	BRIDGE	IL64 AT VILLA AVE.	IL 64 AT ELMHURST PL.	100% VILLA PARK	100% ELMHURST	80% STATE / 20% VILLA PARK	80% STATE / 20% ELMHURST	
				0004	0014	80% FED / 10% STATE / 5% DUPAGE CO / 5% VILLA PARK	100% ELMHURST	SAFETY 0021	SAFETY 0021	SAFETY 0021	SAFETY 0021	
					SN 022-0158							
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	250	250								
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SQ YD	250	250								
42001300	PROTECTIVE COAT	SQ YD	885	885								
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	175	175								
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4140							1242	2898	
44000100	PAVEMENT REMOVAL	SQ YD	1031	1031								
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	196	196								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	848	848								
44000600	SIDEWALK REMOVAL	SQ FT	510	510								
44003100	MEDIAN REMOVAL	SQ FT	1993	1993								
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	13	13								
44201299	DOWEL BARS 1 1/2"	EACH	13	13								
44213200	SAW CUTS	FOOT	63	63								
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1							

URBAN

* - DENOTES SPECIALTY ITEM

FILE NAME: I:\2280\725018 - IL 64 Over Salt Creek\EGD\Cadd Sheets\PI95025.rvt:500.dgn

COLLINS ENGINEERS <small>102 W. Wacker Dr. Suite 400 Chicago, IL 60604 Tel: (312) 784-1300 Fax: (312) 784-3325 www.collins-engineers.com</small> <small>ILLINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 041-020993</small>	USER NAME : rgal1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL ROUTE 64 (NORTH AVE) OVER SALT CREEK SUMMARY OF QUANTITIES	F.A.P. RATE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLLOT SCALE x 2.0000 1/16"	DRAWN -	REVISED -			307	1316-BR	DUPAGE	111	4
	PLLOT DATE : 10/28/2013	CHECKED -	REVISED -			CONTRACT NO. 60V24				
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT				