				CONSTRUCTION CODE							
				80% FEDERAL / 20% STATE		TRAFFIC SIGNALS		ROADWAY LIGHTING / EVP		SIDEWALK	
						IL64 AT VILLA AVE.	IL 64 AT ELMHURST PL.				
						80% FED / 10% STATE / 5% DUPAGE CO / 5% VILLA PARK	100% ELMHURST	100% VILLA PARK	100% ELMHURST	80% STATE / 20% VILLA PARK	80% STATE / 20% ELMHURST
				ROADWAY	BRIDGE	SAFETY	SAFETY	SAFETY	SAFETY	SAFETY	SAFETY
	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0001	0011	0021	0021	0021	0021	0021	0021
						SN 022-0158						
•	89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	2			2					
•	89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	2			1	1				
•	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	4394			3524	870				
•	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2			1	1				
•	89502380	REMOVE EXISTING HANDHOLE	EACH	2			2					
•	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	4			2	2				
	X0323491	SLOPE WALL CRACK SEALING	FOOT	14		14						
•	X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	523					523			
	X0327638	STREAM GAUGE	EACH	2		2						
	X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	1702		1702						
☐	X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	136	136							
☐	X5538200	STORM SEWERS TO BE CLEANED 24"	FOOT	61	61							
☐	X5538600	STORM SEWERS TO BE CLEANED 36"	FOOT	90	90							
	X6330705	RUB RAIL	FOOT	20	20							

• - DENOTES SPECIALTY ITEM

☐ NP- (100% STATE)

FILE NAME = J:\7290\72918.18 - IL 64 Over Salt Creek\CADD\Cadd Sheets\P139328-sht-SOQ.dgn

COLLINS ENGINEERS 123 N. Wacker Dr. Suite 800 Chicago, IL 60606 Phone: (312) 704-1000 Fax: (312) 704-9320 www.collinsengr.com ILLINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 184-000993

USER NAME = rgall	DESIGNED -	REVISED -	
	DRAWN -	REVISED -	
PLOT SCALE = 2.0000 ' / in.	CHECKED -	REVISED -	
PLOT DATE = 10/20/2013	DATE -	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 64 (NORTH AVE) OVER SALT CREEK
SUMMARY OF QUANTITIES

SCALE: | SHEET OF SHEETS | STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	1318-BR	DuPAGE	111	12

CONTRACT NO. 60V24

ILLINOIS FED. AID PROJECT