

PAVMENT SCHEDULE

LOCATION	STATION		AGG SUBGRADE 12" (SQ YD)	STABILIZED SUBBASE-HOT- MIX ASPHALT, 4 1/2" (SQ YD)	PCC PVT 11" JOINTED (SQ YD)	PCC BASE COURSE 8" (SQ YD)
	FROM	TO				
IL 64	94+82.44	104+35.38	250	250	250	250
TOTAL			250	250	250	250

GUARDRAIL SCHEDULE

LOCATION	STATION		OFFSET	TR BAR TRM T1 SPL TAN (EACH)	TR BAR TRM T6 (EACH)	GUARDRAIL MARKERS (EACH)	TERM MARK DIRECT APPLIED
	FROM	TO					
IL 64	98+42.49		RT	1		4	1
IL 64	99+24.60		RT		1		
IL 64	101+05.59		LT		1	4	
IL 64	101+99.61		LT	1			1
TOTAL				2	2	8	2

EARTHWORK SCHEDULE

1	2	3	4	5	6	7
LOCATION	EARTH EXCAVATION	UNSUITABLE OR UNSTABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOP SOIL FURNISH AND PLACE
	CU YD	CU YD	CU YD	CU YD	CU YD	SQ YD
IL 64	185	25	139	80	59	235
TOTAL						

FILE NAME = I:\2010\729018 - IL 64 Over Salt Creek\CADD\Sheets\PI313108-01t-schedule.dgn

COLLINS ENGINEERS
 123 N. Wacker Dr.
 Suite 300
 Chicago, IL 60606
 Phone: (312) 704-9300
 Fax: (312) 704-9300
 www.collinsengr.com
 ILLINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 084-088993

USER NAME = rge11	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -
PLOT DATE = 10/24/2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 64 OVER SALT CREEK
SCHEDULE OF QUANTITIES**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	1318-BR		111	17
CONTRACT NO. 60V24			ILLINOIS FED. AID PROJECT	