



- NOTES:**
- PCC WEDGE TO BE CONSTRUCTED MONOLITHICALLY WITH CURB AND GUTTER. COST TO BE INCLUDED IN THE COST OF COMBINATION CONCRETE CURB AND GUTTER.
 - ELEVATIONS ALONG THE RADIUS OF THE PROPOSED CURB AND GUTTER TO BE DETERMINED IN THE FIELD.
 - SEE ROADWAY LIGHTING PLANS FOR LIGHT POLE RELOCATION DETAILS.

- LEGEND:**
- PAVEMENT WIDENING
PCC PAVEMENT, 11" (JOINTED)
STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"
AGGREGATE SUBGRADE IMPROVEMENT, 12"
 - EXISTING JOINT
 - CONSTRUCTION JOINT
 - - - SAWED JOINT

FILE NAME = I:\2290\729018 - IL 64 Over-Salt Creek\CADD\Sheet\PI39308-shrt-inter-rec.dgn

COLLINS ENGINEERS
123 N. Wacker Dr.
Suite 300
Chicago, IL 60606
Tel: (312) 704-9300
Fax: (312) 704-9320
www.collinseng.com
ILLINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 084-008993

USER NAME = rge11	DESIGNED -	REVISED -
DRAWN -	REVISED -	
PLOT SCALE = 48.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 10/24/2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

ROADWAY DETAILS			
JOINTING PLAN ILLINOIS ROUTE 64 AT VILLA AVE.			
SCALE:	SHEET	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	1318-BR	DuPAGE	111	31
CONTRACT NO. 60V24				
ILLINOIS FED. AID PROJECT				