



SCHEDULE OF QUANTITIES

QUANTITY	UNIT	ITEM
123	FOOT	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA
1	EACH	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION
751	FOOT	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C
1	EACH	DRILL EXISTING HANDHOLE
1528	FOOT	REMOVE ELECTRIC CABLE FROM CONDUIT
777	FOOT	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F
1	EACH	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "EAGLE" TO MATCH THE EXISTING ADJACENT SYSTEM.

I:\3003\DC\NYCADD_Sheets\15171-sht-rs-27.dgn 24-OCT-2013 14:18:15



USER NAME = mgravida	DESIGNED - MG	REVISED -
PLOT SCALE = 40.000000:1.000000	DRAWN - MG	REVISED -
PLOT DATE = 24-OCT-2013 14:18	CHECKED - KGP	REVISED -
	DATE - 10/25/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHMATIC DIAGRAM
ILLINOIS ROUTE 64 (VILLA AVE. TO BERTEAU AVE.)

SCALE: AS NOTED SHEET NO. 25 OF 26 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	131B-BR	DUPAGE	111	68
CONTRACT NO. 60V24			ILLINOIS FED. AID PROJECT	