

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FED 90% STATE 10% ROADWAY	FED 90% STATE 7.5% VILLAGE 2.5% TRAFFIC SIGNALS	FED 90% STATE 10% INTER-CONNECT	VILLAGE 100% EVP	FED 90% STATE 10% LIGHTING	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FED 90% STATE 10% ROADWAY	FED 90% STATE 7.5% VILLAGE 2.5% TRAFFIC SIGNALS	FED 90% STATE 10% INTER-CONNECT	VILLAGE 100% EVP	FED 90% STATE 10% LIGHTING		
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	715		715				87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	750		750					
81400100	HANDHOLE	EACH	8		8				87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2004		2004					
81400200	HEAVY-DUTY HANDHOLE	EACH	4		4				87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3180		3180					
81400300	DOUBLE HANDHOLE	EACH	2		2				87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2015		2015					
81603035	UNIT DUCT, 600V, 2-1/C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA, POLYETHYLENE	FOOT	1150					1150	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3953		3953					
81702417	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6, 1/C NO. 6 GROUND	FOOT	403					403	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	58		58					
81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	708					708	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	922		922					
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	2					2	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1		1					
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3			3			87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2					
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1				87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1		1					
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	4566			4566				SPECIALTY ITEM									

FILE NAME *	USER NAME * SWITHCJ	DESIGNED -	REVISED -
C:\p\dms\work\160809\16081303\15\151-11-0001.dwg		DRAWN -	REVISED -
	PLOT SCALE * 100.0000" = 1"	CHECKED -	REVISED -
	PLOT DATE * 10/18/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL RTE. 62 AT MEACHAM RD.
SUMMARY OF QUANTITIES

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.
SECTION	COUNTY	TOTAL SHEETS
339	COOK	54
CONTRACT NO. 60W05		SHEET NO. 5
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		