

FILE PATH: c:\projects\2013\2013-011R\2013-011R.dwg USER: jtrubley DATE: 11/6/2013

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE					
				ROADWAY	ROADWAY	BRIDGE	LIGHTING	OTHER	
				90% FED	100% STATE	90% FED	10% STATE	90% FED	
				10% STATE	100% STATE	10% STATE	10% STATE	10% STATE	
				0004	0004	0011	0021	0044	
URBAN	URBAN	016-1708	URBAN	URBAN					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	95	95					
44000300	CURB REMOVAL	FOOT	258	258					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	535	535					
44000600	SIDEWALK REMOVAL	SQ FT	15,588	15,588					
44001980	CONCRETE BARRIER REMOVAL	FOOT	507	507					
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1			
50157300	PROTECTIVE SHIELD	SQ YD	1,394			1,394			
50200100	STRUCTURE EXCAVATION	CU YD	3,628	335		3,293			
50300225	CONCRETE STRUCTURES	CU YD	1,123.0	105.3		1,017.7			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	192			192			
50300285	FORM LINER TEXTURED SURFACE	SQ FT	1,212			1,212			
50300300	PROTECTIVE COAT	SQ YD	400			400			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1			
50500505	STUD SHEAR CONNECTORS	EACH	6,806			6,806			

* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICIPATING ITEM



DESIGNED - JLV
 DRAWN - BAW
 CHECKED - JMG
 DATE - 10/30/2013

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET 4 OF 17 SHEETS STA. TO STA.

F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-011R	COOK	356	9
CONTRACT NO. 60W29			ILLINOIS FED. AID PROJECT	