

FILE PATH = p:\AN\28157\pavint\electronic\local\PROJECTS\CONTRACTS\01 - American Transportation Builders Act\Phase 1\INFORM\CONTRACTS\Roadway\Sheets\60W29 - sht - 500.dgn

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE					
				ROADWAY	ROADWAY	BRIDGE	LIGHTING	OTHER	
				90% FED		90% FED	90% FED	90% FED	
				10% STATE	100% STATE	10% STATE	10% STATE	10% STATE	
				0004	0004	0011	0021	0044	
URBAN	URBAN	016-1708	URBAN	URBAN					
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	406	406					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	103	103					
* 78100300	REPLACEMENT REFLECTOR	EACH	387	387					
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	122	122					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	4,536	4,536					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	142	142					
* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	240				240		
* 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	240				240		
* 81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	1,688				1,688		
* 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	515				515		
* 81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	160				160		
* 81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	130				130		
* 81101005	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., PVC COATED GALVANIZED STEEL	FOOT	2,280				2,280		
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	960				960		

* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICIPATING ITEM



0160W29-sht-500.dgn
 USER NAME = JTRubiny
 PLOT SCALE = 20.0000' / 1" =
 PLOT DATE = 11/6/2013

DESIGNED - JLV REVISED -
 DRAWN - BAW REVISED -
 CHECKED - JMG REVISED -
 DATE - 10/30/2013 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET 9 OF 17 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-011R	COOK	356	14
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60W29	