


CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE					
				ROADWAY	ROADWAY	BRIDGE	LIGHTING	OTHER	
				90% FED		90% FED	90% FED	90% FED	
				10% STATE	100% STATE	10% STATE	10% STATE	10% STATE	
				0004	0004	0011	0021	0044	
URBAN	URBAN	016-1708	URBAN	URBAN					
X0327357	CONSTRUCTION VIBRATION MONITORING	L SUM	1	1					
X0327614	COMBINED SEWER REMOVAL 12"	FOOT	4	4					
X0327615	COMBINED SEWER REMOVAL 8"	FOOT	48	48					
X0327616	MAINTAINING ITS DURING CONSTRUCTION	CAL MO	15				15		
* X0370049	UNDERGROUND CONDUIT, PVC, 2" DIA., SCHEDULE 80 (CDOT)	FOOT	1,110				1,110		
X0370069	COMBINED SEWER (EXTRA STRENGTH VITRIFIED CLAY PIPE) 8 INCH (CDOT)	FOOT	100	100					
X0370070	COMBINED SEWER, (WATER MAIN REQUIREMENTS), 8 INCH CDOT	FOOT	169	169					
X0370080	COMBINATION CURB AND GUTTER TYPE B V.12 (CDOT)	FOOT	50	50					
X0370081	SAND CUSHION, 4 INCH, (CDOT)	SQ FT	3,286.0	3,286.0					
** X0370085	CLEAN MANHOLE OR HANDHOLE (CDOT)	EACH	4		4				
X0370135	CONCRETE CURB, TYPE B (SPECIAL) (CDOT)	FOOT	831	831					
X4240800	DETECTABLE WARNINGS (SPECIAL)	SQ FT	12	12					
X5011100	FOUNDATION REMOVAL	EACH	8			8			
X5091730	BRIDGE FENCE RAILING (SPECIAL)	FOOT	129			129			

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

	D:\60W29\sh1-500.dgn USER NAME = JTRubley PLOT SCALE = 20.0000' / 1" = PLOT DATE = 11/6/2013	DESIGNED - JLV DRAWN - BAW CHECKED - JMG DATE - 10/30/2013	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES SCALE: NONE SHEET 12 OF 17 SHEETS STA. TO STA.	F.A.J. RTE. 90/94/290	SECTION 2013-01R	COUNTY COOK	TOTAL SHEETS 356	SHEET NO. 17	CONTRACT NO. 60W29 ILLINOIS FED. AID PROJECT
---	---	---	--	---	---	--------------------------	---------------------	----------------	---------------------	-----------------	---

FILE PATH: D:\60W29\sh1-500.dgn
 PROJECT: ILLINOIS DEPARTMENT OF TRANSPORTATION
 CONTRACT: 60W29
 SHEET: 17 OF 356