

FILE PATH: \\paul.labs.ces.state.il.us\paul\paul\Documents\Illinois\Transportation\60W29\Drawings\Sheet\60W29\_Contract\60W29-Sub-500.dgn

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE					
				ROADWAY	ROADWAY	BRIDGE	LIGHTING	OTHER	
				90% FED		90% FED	90% FED	90% FED	
				10% STATE	100% STATE	10% STATE	10% STATE	10% STATE	
				0004	0004	0011	0021	0044	
URBAN	URBAN	016-1708	URBAN	URBAN					
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	434	205		229			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
Z0062456	TEMPORARY PAVEMENT	SQ YD	849	849					
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	9,382			9,382			
X0327685	COMBINED SEWER REMOVAL 54"	FOOT	77	77					
X0327687	SIPHON RECONSTRUCTION	L SUM	1	1					
X0370185	COMBINED SEWER (EXTRA STRENGTH VITRIFIED CLAY PIPE) 12 INCH (CDOT)	FOOT	4	4					
X7035104	TEMPORARY EPOXY PAVEMENT MARKING - LINE 4"	FOOT	3,395	3,395					
X7035105	TEMPORARY EPOXY PAVEMENT MARKING - LINE 5"	FOOT	1,513	1,513					
X7035108	TEMPORARY EPOXY PAVEMENT MARKING - LINE 8"	FOOT	8,377	8,377					
X7035112	TEMPORARY EPOXY PAVEMENT MARKING - LINE 12"	FOOT	41	41					
X0370074	RACKING CABLES IN MANHOLE OR HANDHOLE (CDOT)	EACH	5				5		
*	GROUND ROD, 3/4" X 10'-0" LENGTH (CDOT)	EACH	8					8	

\* DENOTES SPECIALTY ITEM

\*\* DENOTES NON-PARTICIPATING ITEM



D:\62429\shtr500.dgn	DESIGNED - JLV	REVISED -
USER NAME - JTRubiny	DRAWN - BAW	REVISED -
PLOT SCALE - 20.0000' / 1"	CHECKED - JMG	REVISED -
PLOT DATE - 11/6/2013	DATE - 10/30/2013	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NONE	SHEET 15	OF 17	SHEETS	STA.	TO STA.	F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
						90/94/290	2013-011R	COOK	356	20
										CONTRACT NO. 60W29
ILLINOIS FED. AID PROJECT										