

FILE PATH: C:\Users\paul.lafayette\Documents\Illinois\Projects\Phase 11\000_CDD\006_Peasava\Status\000\03_Contract\1106\079-ant-500.dgn

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE					
				ROADWAY	ROADWAY	BRIDGE	LIGHTING	OTHER	
				90% FED		90% FED	90% FED	90% FED	
				10% STATE	100% STATE	10% STATE	10% STATE	10% STATE	
				0004	0004	0011	0021	0044	
URBAN	URBAN	016-1708	URBAN	URBAN					
* X0370075	UNDERGROUND CONDUIT, PVC, 4" DIA., SCHEDULE 80 (CDOT)	FOOT	2,525				2,525		
* X0370186	ELECTRICAL MANHOLE, 3' X 4' X 4', 30" FRAME AND LID (CDOT)	EACH	2				2		
* 83000023	LIGHT POLE, ALUMINUM, 18 FT. M.H., 8 FT. DAVIT ARM	EACH	12				12		
* 83000024	LIGHT POLE, ALUMINUM, 18 FT. M.H., 8 FT. DAVIT ARM - TWIN	EACH	2				2		
X0327688	REMOVAL OF ETU BOLLARD FOUNDATION	EACH	2				2		
* X0370076	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM	FOOT	160				160		
** X0327689	COMBINED SEWERS TO BE CLEANED, SPECIAL	FOOT	930		930				
* X0324571	MAINTENANCE OF STREET LIGHTING SYSTEM (CITY OF CHICAGO)	LSUM	1				1		
X0327690	TELEVISION INSPECTION OF SEWER, SPECIAL	FOOT	1,860	1,860					
X0370187	CONCRETE (CTA)	LSUM	1					1	
X0370188	DEMOLITION (CTA)	LSUM	1					1	
X0370189	STRUCTURAL STEEL AND METAL DECK (CTA)	LSUM	1					1	
X0370190	MASONRY (CTA)	LSUM	1					1	
X0370191	ELEVATOR (CTA)	LSUM	1					1	

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM



D:\02\29-ant-500.dgn
 USER NAME = JTRubley
 PLOT SCALE = 28.2828' / in.
 PLOT DATE = 11/6/2013

DESIGNED - JLV
 DRAWN - BAW
 CHECKED - JMC
 DATE - 10/30/2013

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET 16 OF 17 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-011R	COOK	356	21
CONTRACT NO. 60W29				
ILLINOIS FED. AID PROJECT				