

**SIGNING SCHEDULE**

LOCATION	SIGN NO.	LEGEND / DESCRIPTION	CODE	ACTION	LOCATION (STATION / OFFSET)		EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		NUMBER OF POSTS	REMOVE SIGN PANEL - TYPE 1 (SQ FT)	REMOVE SIGN PANEL - TYPE 2 (SQ FT)	REMOVE OVERHEAD SIGN STRUCTURE - WALKWAY (FOOT)	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED (EACH)	REMOVE SIGN PANEL ASSEMBLY - TYPE A (EACH)	REMOVE SIGN PANEL ASSEMBLY - TYPE B (EACH)	SIGN PANEL - TYPE 1 (SQ FT)	SIGN PANEL - TYPE 2 (SQ FT)	SIGN PANEL - TYPE 3 (SQ FT)	STEEL POSTS, SPECIAL (EACH)	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED (FT)	TELESCOPING STEEL SIGN SUPPORT (FT)
					EXISTING	PROPOSED	WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)													
PEORIA STREET	PEO-01-ST	CTA BUS STOP	CUSTOM	EXISTING SIGN TO REMAIN	3700+06	69.03' LT	-	-	1.50	2.00	-	-	1										
	PEO-02-LP	PEDESTRIAN CROSSING	W11-2	EXISTING SIGN TO REMAIN	3700+06	47.33' LT	-	-	2.50	2.50	-	-											
	PEO-03-LP	TOW ZONE	R7-201-4	EXISTING SIGN TO REMAIN	3700+06	27.86' RT	-	-	1.50	1.50	-	-											
	PEO-04-CP	UIC	CUSTOM	REMOVE AND REPLACE SIGN (SEE NOTE 1)	3700+56	3.39' LT	(BY OTHERS)		3.33	9.00	3.33	9.00											
	PEO-05-ST	UIC MAP	CUSTOM	REMOVE AND REPLACE SIGN (SEE NOTE 1)	3702+38	0.16' RT	(BY OTHERS)		2.92	2.92	2.92	2.92	1										
	PEO-06-ST	NO PETS ALLOWED	CUSTOM	REMOVE AND REPLACE SIGN (SEE NOTE 1)	3702+58	45.03' RT	(BY OTHERS)		1.50	1.00	1.50	1.00	1										
	PEO-07-ST	NO PARKING-ANY TIME	R7-4	REMOVE	3703+18	21.20' LT	-	-	1.50	1.00	-	-	1				1						
	PEO-08-ST	NO PARKING-ANY TIME	R7-4	REMOVE	3703+18	21.02' RT	-	-	1.00	1.50	-	-	1				1						
	PEO-09-ST	WELCOME TO UIC	CUSTOM	REMOVE AND REPLACE SIGN (SEE NOTE 1)	3703+56	26.14' RT	(BY OTHERS)		3.92	4.58	3.92	4.58	2										
	PEO-10-ST	HANDICAP ACCESS	CUSTOM	REMOVE AND REPLACE SIGN (SEE NOTE 2)	3703+99	9.38' RT	(BY OTHERS)		1.00	1.50	1.00	1.50	2										
	PEO-11-ST	CTA BLUE LINE UIC-HALSTED	CUSTOM	REMOVE AND REPLACE SIGN (SEE NOTE 2)			(BY OTHERS)		0.33	1.42	0.33	1.42											
	PEO-12-ST	TOW ZONE	R7-201-4	REMOVE	3704+03	2.59' LT	-	-	1.50	1.00	-	-	1				1						
	PEO-13-LP	TOW ZONE	R7-201-1/3	REMOVE	3705+14	20.99' LT	-	-	1.50	1.50	-	-		2.25									
	PEO-14-LP	TOW ZONE	R7-201-1/3	REMOVE	3705+15	21.12' RT	-	-	1.50	1.00	-	-		1.50									
	PEO-15-ST	TOW ZONE	R7-201-1/3	REMOVE	3705+52	20.68' LT	-	-	1.50	1.50	-	-	1				1						
	PEO-16-ST	UIC SIGN	CUSTOM	REMOVE AND REPLACE SIGN (SEE NOTE 1 & 3)	3706+37	22.89' LT	(SEE NOTE 3)		4.83	3.75	4.83	3.75	2										
	PEO-17-LP	NO PARKING/LOADING ZONE	R7-601-93	REMOVE	3706+38	20.89' RT	-	-	1.50	1.00	-	-	1	1.50									
	PEO-18-ST	NO PARKING / TOW ZONE	R7-201-4	REMOVE	3706+52	20.85' LT	-	-	1.50	1.50	-	-	1				1						
	PEO-19-ST	NO PARKING / TOW ZONE	R7-201-4	REMOVE AND REPLACE SIGN	3706+79	20.17' LT	3706+82	21.50' LT	1.50	1.50	1.50	1.50	1				1		2.25			1	
	PEO-20-ST	NO PARKING / TOW ZONE / LEFT ARROW	R7-201-3	REMOVE AND REPLACE SIGN	3707+07	20.98' RT	3706+87	20.75' RT	1.50	1.50	1.50	1.50	1				1		2.25			1	
	PEO-21-ST	NO PARKING/LOADING ZONE	R7-601-91	REMOVE	-	-	-	-	1.50	1.00	-	-											
	PEO-22-ST	UIC SIGN	CUSTOM	EXISTING SIGN TO REMAIN	3707+23	22.84' LT	-	-	4.75	2.75	-	-	2										
	PEO-23-LP	STOP	R1-1-2	EXISTING SIGN TO REMAIN	3707+48	21.15' RT	-	-	3.00	3.00	-	-	1										
	PEO-24-LP	STOP	R1-1-2	EXISTING SIGN TO REMAIN			-	-	3.00	3.00	-	-		-	-								
	PEO-25-ST	UIC SIGN	CUSTOM	EXISTING SIGN TO REMAIN	3707+53	32.15' RT	-	-	4.75	2.75	-	-	2										
EB I-290	EB-01-BM	I-90/94 WEST KENNEDY EXPY - WISCONSIN	CUSTOM	PROPOSED SIGN	-	-	339+10	5.33' RT	-	-	23.00	11.50							264.50			15	
	EB-02-BM	I-90/94 EAST RYAN EXPY - INDIANA	CUSTOM	PROPOSED SIGN	-	-	339+12	25.36' RT	-	-	19.50	11.00							214.50			15	
	EB-03-BM	I-90/94 WEST KENNEDY EXPY - WISCONSIN	CUSTOM	REMOVE	345+53	5.60' RT	-	-	16.50	10.50	-	-		17	1								
	EB-04-BM	I-90/94 EAST RYAN EXPY - INDIANA	CUSTOM	REMOVE	345+53	24.00' RT	-	-	17.00	10.50	-	-		17	1								
	EB-05-BM	PEORIA STREET 900 W	CUSTOM	REMOVE AND REPLACE SIGN	345+53	39.46' RT	345+50	52.00' RT	6.00	2.00	7.00	2.50		12.00					17.50				
	EB-06-BM	NO PANEL	-	-	345+53	11.70' LT	-	-	-	-	-	-		17	-								
WB I-290	WB-01-BM	EXIT 28B - ASHLAND AVE/PAULINA ST 3/4 MILE	CUSTOM	REMOVE & RELOCATE	346+02	0.00' RT	-	-	19.00	9.50	-	-		19	1								
	WB-02A-BM	EXIT 28B	CUSTOM	PROPOSED SIGN	-	-	346+02	0.00' RT	-	-	11.50	2.50							28.75			17	
	WB-02B-BM	ASHLAND AVE 3/4 MILE	CUSTOM	PROPOSED SIGN	-	-	346+02	0.00' RT	-	-	17.00	6.00							102.00				
	WB-03A-BM	EXIT 29B	CUSTOM	REMOVE AND REPLACE SIGN	346+00	26.86' LT	346+02	55.26' LT	18.00	7.50	11.50	2.50		18	1					28.75		18	
	WB-03B-BM	MORGAN ST 1000 W	CUSTOM	REMOVE AND REPLACE SIGN	346+00	26.86' LT	346+02	55.26' LT	18.00	7.50	17.50	5.00							87.50				
	WB-04-TS	PEORIA STREET 900 W	CUSTOM	REMOVE AND REPLACE SIGN	346+08	45.66' LT	346+02	66.16' LT	6.00	2.00	7.00	2.50					1		17.50				35
WB-05-LP	AMERICAN BYWAYS	D6-4	EXISTING SIGN TO REMAIN	346+75	49.11' LT	-	-	2.00	2.00	-	-												
<b>TOTAL</b>												<b>6</b>	<b>12</b>	<b>88</b>	<b>4</b>	<b>7</b>	<b>1</b>	<b>5</b>	<b>35</b>	<b>726</b>	<b>2</b>	<b>65</b>	<b>35</b>

**NOTES:**

- SIGN PANEL TO BE REMOVED. CONTRACTOR TO PROVIDE 2 WEEKS ADVANCE NOTICE PRIOR TO SIGN PANEL REMOVAL AND TO PROVIDE THE ENTIRE SIGN PANEL AND POSTS TO A DESIGNATED UNIVERSITY OF ILLINOIS AT CHICAGO STORAGE LOCATION IN THE SAME CONDITION PRIOR TO REMOVAL.
- SIGN PANEL TO BE REMOVED BY THE CTA. CONTRACTOR SHALL COORDINATE WITH THE CTA PRIOR TO BEGINNING CONSTRUCTION ACTIVITIES WHICH WOULD IMPACT THE SIGN PANEL.
- SIGN PANEL TO BE RETRIEVED FROM THE DESIGNATED UNIVERSITY OF ILLINOIS AT CHICAGO STORAGE LOCATION AND PLACED IN THE FINAL LOCATION AS APPROVED BY THE RE. IF NO FINAL LOCATION HAS BEEN APPROVED, SIGN TO BE LEFT IN STORAGE.

FILE PATH = p:\388035-p\mt\escomon\me\local\PECD\000\Documents\01\_Americas\Transportation\60269938\_Circle\Phase\_1\000\_CAD\005\_Roadway\Sheets\60W29-sht-Sign-Schedule-01.dgn



D:\60W29-sht-Sign-Schedule-01.dgn	DESIGNED - JDT	REVISED -
USER NAME = BAW1tor t	DRAWN - JTR	REVISED -
PLOT SCALE = 20.0000' / in.	CHECKED - JMG	REVISED -
PLOT DATE = 10/28/2013	DATE - 10/30/2013	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SIGNING PLAN SCHEDULE</b>			
SCALE: NONE	SHEET 1	OF 4 SHEETS	STA. TO STA.

F.A.I. RTE. 90/94/290	SECTION 2013-011R	COUNTY COOK	TOTAL SHEETS 356	SHEET NO. 99
CONTRACT NO. 60W29			ILLINOIS FED. AID PROJECT	