


SANGAMON ST.

PEORIA ST.



EXISTING ITS CABINET G1.
TERMINATE NEW POWER AND
COMM. CABLES IN EXISTING
CABINET (INCIDENTAL TO
CABLE ITEM).

(2) 287 FT. OF 3" PVC CONDUIT
WITH
(1) 6/C #19 COMM. CABLE
(2) 2/C #6 WITH #8 GROUND
POWER CABLES

(2) 120 FT. OF 3" GS CONDUIT
WITH
(1) 6/C #19 COMM. CABLE
(2) 2/C #6 WITH #8 GROUND
POWER CABLES

(2) 484 FT. OF 3" PVC CONDUIT
WITH
(1) 6/C #19 COMM. CABLE
(2) 2/C #6 WITH #8 GROUND
POWER CABLES

(2) 73 FT. OF 3" PVC CONDUIT
WITH
(1) 6/C #19 COMM. CABLE
(2) 2/C #6 WITH #8 GROUND
POWER CABLES

(2) 198 FT. OF EXISTING CONDUIT
WITH
(1) 6/C #19 COMM. CABLE
(2) 2/C #6 WITH #8 GROUND
POWER CABLES

(2) 349 FT. OF EXISTING CONDUIT
WITH
(1) 6/C #19 COMM. CABLE
(1) 2/C #6 WITH #8 GROUND
POWER CABLES

EXISTING ITS CABINET Z1.
TERMINATE NEW POWER AND
COMM. CABLES IN EXISTING
CABINET (INCIDENTAL TO
CABLE ITEM).

EXISTING ITS CABINET Z3.
TERMINATE NEW POWER AND
COMM. CABLES IN EXISTING
CABINET (INCIDENTAL TO
CABLE ITEM).

SEE DETAIL A

WB I-290

EB I-290

HALSTED ST

345+00

345+00
100+00

7300+00

125+00

DETAIL A

FILE PATH = p:\388035\pmt\aecon\line\local\p\AECON\Documents\01_Americas\Transportation\60269938_Circle\Phase_1\000_CAD\005_Roadway_Sheets\60W29_sht-ITS-03



DI60W29-sht-ITS-03
USER NAME = BAW:tor t
PLOT SCALE = 60.0000' / in.
PLOT DATE = 10/28/2013

DESIGNED - JML	REVISED -
DRAWN - JML	REVISED -
CHECKED - WDS	REVISED -
DATE - 10/30/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PROPOSED ITS PLAN
I-290

SCALE: 1" = 30' SHEET 3 OF 3 SHEETS STA. 342+26 TO STA. 351+80

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-011R	COOK	356	132
CONTRACT NO. 60W29				
ILLINOIS FED. AID PROJECT				