

T:\16843A\CCTV\Files from NY\19-17-2013\12-strand-laterals.dgn
19-DEC-2013 18:15

LATERAL CABLE FIBER ASSIGNMENTS		
LCF-EBH		
FIBER NO	FUNCTION	CONNECTION
1	CCTV CAMERA IKOA (at Southeast Bridge House)	Fiber #1 of 96-strand SubM trunk cable
2	CCTV CAMERA IKOB (at Southeast Bridge House)	Fiber #2 of 96-strand SubM trunk cable
3	DARK	
4	DARK	
5	DARK	
6	DARK	
7	DARK	
8	DARK	
9	DARK	
10	DARK	
11	DARK	
12	DARK	

LATERAL CABLE FIBER ASSIGNMENTS		
LCF-SJS		
FIBER NO	FUNCTION	CONNECTION
1	CCTV CAMERA IKOE (at So. Jefferson St.)	Fiber #7 of 24-strand West trunk cable
2	CCTV CAMERA IKOF (at So. Jefferson St.)	Fiber #8 of 24-strand West trunk cable
3	DARK	
4	DARK	
5	DARK	
6	DARK	
7	DARK	
8	DARK	
9	DARK	
10	DARK	
11	DARK	
12	DARK	

LATERAL CABLE FIBER ASSIGNMENTS		
LCF-WBH		
FIBER NO	FUNCTION	CONNECTION
1	CCTV CAMERA IKOC (at Northwest Bridge House)	Fiber #3 of 96-strand West trunk cable
2	CCTV CAMERA IKOD (at Northwest Bridge House)	Fiber #4 of 96-strand West trunk cable
3	DARK	
4	DARK	
5	DARK	
6	DARK	
7	DARK	
8	DARK	
9	DARK	
10	DARK	
11	DARK	
12	DARK	

LATERAL CABLE FIBER ASSIGNMENTS		
LCF-dms		
FIBER NO	FUNCTION	CONNECTION
1	ETHERNET - Tx	Fiber #5 of 96-strand West trunk cable
2	ETHERNET - Rx	Fiber #6 of 96-strand West trunk cable
3	DARK	
4	DARK	
5	DARK	
6	DARK	
7	DARK	
8	DARK	
9	DARK	
10	DARK	
11	DARK	
12	DARK	

PARSONS BRINCKERHOFF
230 West Monroe Street
Suite 900
Chicago, IL 60606

USER NAME - pstald	DESIGNED - D. DRAKULICH	REVISED - 12/20/2013 D.C.P.
FILE NAME	DRAWN - E. MALUSEL	REVISED -
PLOT SCALE - NONE	CHECKED - S. STERN	REVISED -
PLOT DATE - 10/18/2013	DATE - 10/18/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CCTV SYSTEM, I-90/94 TO CONGRESS PARKWAY
TWENTY FOUR LATERAL CABLE FIBER ASSIGNMENTS

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. 353+46.00 TO STA. 382+50.00

F.A.P. RTE. 389	SECTION 2013-026-1	COUNTY COOK	TOTAL SHEETS 37	SHEET NO. 23
CONTRACT NO. 60W49				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				