

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	83	83					
25200110	SODDING, SALT TOLERANT	SO YD	83	83					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	74	74					
40600300	AGGREGATE (PRIME COAT)	TON	367	367					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	138	138					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3778	3778					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	517	517					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	8976	8976					
42001300	PROTECTIVE COAT	SO YD	167	167					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	800	800					
42400800	DETECTABLE WARNINGS	SO FT	500	500					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	91583	91583					

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		0005					
44000600	SIDEWALK REMOVAL	SO FT	800	800					
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	650	650					
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	440	440					
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	1200	1200					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	10	10					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	20	20					
60406000	FRAMES AND LIDS, TYPE I, OPEN LID	EACH	7	7					
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	7	7					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					

18

FILE NAME *	USER NAME * hampton	DESIGNED -	REVISED -
CDR_wat11/10/hampton/034509-Q14513-011-proj.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
IL. RTE. 43 (HARLEM AVE.) / 155 TO 63RD ST.			
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	(3130(A&B) & 2324.3)RS-3	Cook	42	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60W61	

Rev.