SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: COOK 0014	DUPAGE 0014				
50102400	CONCRETE REMOVAL	CU YD	1.1	1.1					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1.1	1.1					
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	27630	27630					
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	4	2				
67100100	MOBILIZATION	L SUM	1	0.75	0.25				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.8	0.2				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	839	839					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	162.5	162.5					
* 73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	24	24					
* 73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	1	1					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	182	182					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: COOK 0014	DUPAGE 0014				
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	29	29					
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	14	14					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	211	211					
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.67	0.33				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.67	0.33				
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	839	839					
* X7200053	REMOVE, STORE AND RE-ERECT SIGN PANEL (SPECIAL)	EACH	1	1					
* X8040150	REMOVAL ELECTRICAL CONNECTION TO SIGN STRUCTURE	EACH	1	1					
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	25030	25030					
Z0001905	STRUCTURAL STEEL REPAIR	POUND	700	700					
Z0003600	BEAM STRAIGHTENING	L SUM	1	0.75	0.25				
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	231.3	179.9	51.4				
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	L SUM	1	1					

*Specialty Items

Rev.

FILE NAME = c:\pw_work\pw160\sey00ecp\d0304B9D\40013-sht-50.dgn	USER NAME = SEYWOPECP	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0000 ' / in.	DRAWN -	REVISED -			VAR.	2013-044BR	COOK & DUPAGE	35	3
	PLOT DATE = 10/30/2013	CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 60W94		
		DATE -	REVISED -			FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		