



PUSHBUTTON NOTES:

PUSHBUTTON "A" SHALL PLACE A CALL IN PHASES 2 AND 4

I. D. O. T. TRAFFIC SIGNAL INSTALLATION ELECTRICAL SERVICE REQUIREMENTS					
TYPE	NO. LAMPS	WATTAGE INCAND.	LED	%OPERATION	TOTAL WATTAGE
SIGNAL (RED)	9		17	0.50	76.5
(YELLOW)	9		25	0.25	56.25
(GREEN)	9		15	0.25	33.75
ARROW	0		12	0.10	0
PED SIGNAL	8		25	1.00	200.0
CONTROLLER	1	100		1.00	100.0
VIDEO SYSTEM	0	150		1.00	0
BATTERY BACKUP	1	25		1.00	25.0
TOTAL =					491.5
ENERGY COSTS-		BILLED TO: IDOT DISTRICT 1			
		201 WEST CENTER COURT			
		SCHAUMBURG, IL 60196-1096			
ENERGY SUPPLY-		CONTACT BRAD SHINABARGAR			
		PHONE 708-325-2692			
		COMMONWEALTH EDISON			

SCHEDULE OF QUANTITIES		UNIT	QUANTITY
ITEM			
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION		EACH	1
MODIFY EXISTING CONTROLLER CABINET		EACH	1
UNINTERRUPTABLE POWER SUPPLY, SPECIAL		EACH	1

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES, CABLE PLAN & PHASE DESIGNATION DIAGRAM
GREGORY ST. AT YORK RD.

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTÉ.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2013-052TS	COOK	87	22
CONTRACT NO. 60X24				
ILLINOIS FED. AID PROJECT				

TS #4560
BLUE ISLAND

FILE NAME = D160X24-sht-ts.TS4560.dgn	USER NAME = Brian Scifers	DESIGNED KJP DRAWN DLW	REVISED -
Default	PLOT SCALE = 40.0000' / in.	CHECKED BKS DATE -	REVISED -
	PLOT DATE = 10/8/2013		REVISED -