

CODE NO.	ITEM	UNIT	URBAN		
			TOTAL QUANTITY	90% FEDERAL 10% STATE	CONSTRUCTION CODE 0021 100% EVP (PLEASANTVIEW FIRE DEPT.)
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1	1	
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1	1	
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1	1	
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1	1	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16	16	
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4	4	
87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	48	48	
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6	6	
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4	4	
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	4	4	
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10	10	
88500100	INDUCTIVE LOOP DETECTOR	EACH	10	10	
88600100	DETECTOR LOOP, TYPE I	FOOT	685	685	
88700200	LIGHT DETECTOR	EACH	2		2
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		1
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1	

FILE NAME *	USER NAME * USER*	DESIGNED - JAM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES JOLIET ROAD AT WOLF ROAD			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
FILEL*		DRAWN - JAM	REVISED -					3562	2013-060T5	COOK	26	05	
MODEL NAME*	PLOT SCALE * SCALE*	CHECKED - LMM	REVISED -		SCALE: NONE	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 60X32		
	PLOT DATE * DATE*	DATE - 10-10-13	REVISED -		ILLINOIS FED. AID PROJECT								