

| SUMMARY OF QUANTITIES | | | | FUNDING: 80% FED : 20% STATE | |
|-----------------------------------|---------------------------------------|-------|----------|------------------------------|--------------------------------------|
| CONSTRUCTION CODE TYPE: | | | TOTAL | 0004 | 0011 |
| CODE NO. | ITEM | UNIT | QUANTITY | ROADWAY | SN 008-0014 (EX) SN 008-0051 (PR) |
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | 78 | 78 | |
| 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER) | UNIT | 110 | 110 | |
| 20200100 | EARTH EXCAVATION | CU YD | 1465 | 1465 | |
| 20400800 | FURNISHED EXCAVATION | CU YD | 7330 | 7330 | |
| * 25000210 | SEEDING, CLASS 2A | ACRE | 1.5 | 1.5 | |
| * 25000310 | SEEDING, CLASS 4 | ACRE | 0.5 | 0.5 | |
| <input type="checkbox"/> 25000750 | MOWING | ACRE | 1.25 | 1.25 | |
| * 25100125 | MULCH, METHOD 3 | ACRE | 0.5 | 0.5 | |
| * 25100630 | EROSION CONTROL BLANKET | SQ YD | 3284 | 3284 | |
| 25100900 | TURF REINFORCEMENT MAT | SQ YD | 342 | 342 | |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 336 | 336 | |
| 28000305 | TEMPORARY DITCH CHECKS | FOOT | 500 | 500 | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 1361 | 1361 | |
| 28000500 | INLET AND PIPE PROTECTION | EACH | 2 | 2 | |

NP-100% STATE

SPECIALTY ITEMS